

**SUMMARY OF QUANTITIES - FAS 731 (SCOTTVILLE TO MODESTO)**

CODE #	PAY ITEM	UNIT	100% STATE 1000 QUANTITY
<del>20005110</del>	<i>HOT-MIX ASPHALT</i> MIXTURE FOR STABILIZED BASE, CA-7 MIX	TON	15,464
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	158
25000200	SEEDING, CLASS 2	ACRE	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	68
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	68
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	68
25000700	AGRICULTURAL GROUND LIMESTONE	TON	2
25100115	MULCH, METHOD 2	ACRE	0.75
35800100	PREPARATION OF BASE	SQ YD	590
40300400	BITUMINOUS MATERIALS (COVER AND SEAL COAT)	TON	131
40300600	SEAL COAT AGGREGATE	TON	915
40600200	<i>MATERIALS</i> BITUMINOUS (PRIME COAT)	TON	35
40600300	AGGREGATE (PRIME COAT)	TON	183
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	120
40600990	TEMPORARY RAMP	SQ YD	500

**NOTES:**

- 1) HMA SHOULDER CONSTRUCTION/SEEDING ONLY FROM STATION 11+95 TO 91+15
- 2) 3" HMA MIXTURE FOR STABILIZED BASE WITH A-1 SURFACE TREATMENT (OIL & CHIP), AGGREGATE SHOULDER, STRIPING, AND OTHER RELATED WORK FROM STATION 11+95 TO 353+76