SUMMARY OF QUANTITIES - FAS 731 (SCOTTVILLE TO MODESTO)

	CODE #	PAY ITEM	UNIT	100% STATE IOOO QUANTITY
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	8
	48101200	AGGREGATE SHOULDERS, TYPE B	TON	2.528
	48203033	HOT-MIX ASPHALT SHOULDERS, 9"	SQ YD	5,264
	67100100	MOBILIZATION	L SUM	1
	70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1
	70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	4
*	78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	76,200
	78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	1,710

NOTES:

1) HMA SHOULDER CONSTRUCTION/SEEDING ONLY FROM STATION 11+95 TO 91+15
2) 3" HMA MIXTURE FOR STABILIZED BASE WITH A-1 SURFACE TREATMENT (OIL & CHIP), AGGREGATE SHOULDER, STRIPING, AND OTHER RELATED WORK FROM STATION 11+95 TO 353+76

* SPECIALTY ITEM

FILE NAME = c:\pw_work\PWIDOT\LAUGHLINRL\d0190078\D72D45-sht-S00.dgn	USER NAME = laughlinrl	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = Apr-08-2010 01:56:24PM	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
731	(1)1-3	MACOUPIN	18	4
		CONTRACT NO. 72D45		
		ILLINOIS FED. AID PROJECT		