

GENERAL NOTES

1. ANY REFERENCE TO THE STANDARDS THROUGH OUT THE PLANS SHALL BE INTERPRETED TO BE THE LATEST STANDARDS OF THE DEPARTMENT AS INCLUDED IN THE PLANS.
2. EXISTING TRAFFIC SIGNAL FIBER OPTIC CABLE IS PRESENT WITHIN THE LIMITS OF THIS PROJECT, THE CONTRACTOR IS RESPONSIBLE FOR CONTACTING J.U.L.I.E. A MINIMUM OF 48 HOURS PRIOR TO COMMENCING WORK TO HAVE THIS CABLE LOCATED. 1-800-892-0123
3. THE CONTRACTOR WILL BE REQUIRED TO CONTACT THE OPERATIONS ENGINEER (217) 782-7314 AT LEAST 72 HOURS PRIOR TO DRIVING ANY POSTS.
4. THE CONTRACTOR WILL BE REQUIRED TO REPAIR ANY AREAS OF TURF THAT ARE DAMAGED DURING THE EXECUTION OF THIS CONTRACT.
5. ALL GUARDRAIL SHALL HAVE A PRELIMINARY LAYOUT. GUARDRAIL POSTS SHALL BE ADJUSTED SO AS TO MISS ANY SHOULDER DRAINS, INLETS, PIPE CULVERTS, STORM SEWER, FIBER OPTIC INTERCONNECT CABLE OR ANY OTHER HAZARD THAT MAY INTERFERE WITH GUARDRAIL CONSTRUCTION.

INDEX OF SHEETS	
SHEET NO.	DISCRIPTION
1	COVER SHEET
2	GENERAL NOTES
3	SUMMARY OF QUANTITIES
3	SCHEDULE OF QUANTITIES
4	PLAN SHEET
5	HOLE PLACEMENT DETAILS

DISTRICT SIX	
EXAMINED <i>[Signature]</i> <u>3/22</u> 20 <u>10</u>	
OPERATIONS ENGINEER	
EXAMINED <u>March 17</u> 20 <u>10</u>	
<i>2RML-1</i>	
PROGRAM DEVELOPMENT ENGINEER	
EXAMINED <u>MARCH 19</u> 20 <u>10</u>	
<i>[Signature]</i>	
PROGRAM IMPLEMENTATION ENGINEER	