

ILLINOIS DEPARTMENT OF TRANSPORTATION						
SUMMARY OF QUANTITIES						
LOCATION OF WORK			URBAN SF7Y-3J		CONSTRUCTION CODE TYPE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SAFETY FUNDS 90% FED 10% STATE		
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	250	250		
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	2	2		
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2		
67100100	MOBILIZATION	L SUM	1	1		
78200410	GUARDRAIL MARKER, TYPE A	EACH	8	8		
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2		
K100910	VEGETATION CONTROL SYSTEM	SQ YD	176	176		

GUARDRAIL SCHEDULE						
LOCATION			OFFSET	STEEL PLATE BEAM GUARD RAIL	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	TRAFFIC BARRIER TERMINAL, TYPE 2
STATION	TO	STATION	LT / RT	FOOT	EACH	EACH
443+05.55	-	443+55.55	RT 14'		1	
443+55.55	-	444+80.55	RT 14'	125		
444+80.55	-	444+93.05	RT 14'			1
444+87.45	-	444+99.95	LT 14.5'			1
444+99.95	-	446+24.95	LT 14.5'	125		
446+24.95	-	446+74.95	LT 14.5'		1	
TOTAL =				250	2	2

VEGETATION CONTROL SCHEDULE				
LOCATION			OFFSET	VEGETATION CONTROL SYSTEM
STATION	TO	STATION	LT / RT	SQ YD
443+00.00	-	444+98.00	RT 14'	88
444+82.00	-	446+80.00	LT 14.5'	88
TOTAL =				176