

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX, STANDARDS, GENERAL NOTES, & SIGNATURES
- 3 SUMMARY OF QUANTITIES
- 4-5 GUARD RAIL SCHEDULE
- 6 LOCATION MAP
- 7 STEEL RAIL, TYPE T-1 DETAILS

GENERAL NOTES:

THE CONTRACTOR SHALL REPLACE ALL GUARD RAIL AND BRIDGE RAIL ON THE SAME DAY THAT IT IS REMOVED. NO OVERNIGHT LANE CLOSURES WILL BE PERMITTED.

ALL STEEL PLATE BEAM GUARDRAIL THAT ARE PLACED ON TOP OF EXISTING RETAINING WALLS SHALL USE 6' POSTS.

THE INCLUDED QUANTITY FOR FURNISHED EXCAVATION, SPECIAL IS INTENDED FOR BUILDING UP SHOULDERS THAT ARE TOO NARROW OR STEEP TO ACCOMODATE TRAFFIC BARRIER TERMINALS. THE ENGINEER SHALL DECIDE WHERE FURNISHED EXCAVATION IS NECESSARY. THE FURNISHED EXCAVATION, SPECIAL PAY ITEM SHALL ALSO INCLUDE ALL LABOR AND MATERIAL NECESSARY TO APPLY CLASS 2 SEEDING TO THE FURNISHED EXCAVATION SPECIAL AREAS AS DETAILED IN THE SPECIAL PROVISIONS.

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

AGGREGATE BACKFILL USED IN GUARDRAIL POST FOUNDATIONS IN ANY ROCK AREAS SHALL BE CA-11.

STANDARDS

- 630001-08
- 630101-08
- 630301-05
- 635006-03
- 635011-02
- 701001-02
- 701006-03
- 701201-03
- 701901-01
- BLR27-1

<b>DISTRICT SIX</b>	
EXAMINED <u>March 16</u>	20 <u>10</u>
<i>Chris Walker</i>	
OPERATIONS ENGINEER	
EXAMINED <u>MARCH 18</u>	20 <u>10</u>
<i>Jimmy F. L.</i>	
PROGRAM IMPLEMENTATION ENGINEER	
EXAMINED <u>March 15</u>	20 <u>10</u>
<i>QRM L</i>	
PROGRAM DEVELOPMENT ENGINEER	

FILE NAME =	USER NAME = madonjavj	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>GENERAL NOTE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cd:\pvt\work\NPWIDOT\MADONJAVJ\0183217\06	2099-shr-gennotes.dgn	DRAWN -	REVISED -			510	120 GUARDRAIL-1	HANCOCK	7	2	
	PLOT SCALE = 40.0000' / IN.	CHECKED -	REVISED -			CONTRACT NO. 72D59					
	PLOT DATE = Mar-11-2010 08:01:51AM	DATE -	REVISED -			ILLINOIS FED. AID PROJECT					
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.			