

GUARDRAIL SCHEDULE

LOCATION	STATION TO STATION		SIDE	63100167	63100169	63100075	X0325194	6E+07	6E+07	IMPACT ATTEN. (FULLY REDIRECTIVE, NARROW) TL3, SPC	SPBGR, 6' POSTS	SPBGR, 9' POSTS	63200310	78201000	78200410	20200100	20200200
				TRAF. BARR. TERM TY 1 SPC. (TANGENT)	TRAF. BARR. TERM TY 1 SPC. (FLARED)	TRAF. BARR. TERM. TY 5A	GUARDRAIL REMOVAL	TERMINAL MARKERS-DIRECT APPLIED	GUARDRAIL MARKERS				EARTH EXCAVATION	ROCK EXCAVATION			
				EACH	EACH	EACH	FOOT	EACH	EACH				CU YD	CU YD			
LOC #1	538+00	551+00	RT										1200.00				
	539+00	539+50	RT	1										1			
	539+50	550+50	RT								1100.00				14		
	550+50	539+50	RT	1										1			
LOCATION #1 SUB-TOTALS				2							1100.00		1200.00	2	14		
LOC #2	564+00	569+00	RT										500.00				
	564+00	564+50	RT	1										1			
	564+50	568+50	RT						450.00						6		
	568+50	569+00	RT	1										1			
LOCATION #2 SUB-TOTALS				2				450.00					500.00	2	6		
LOC #3	571+95	572+45	LT										50.00				
	EARTH EX	571+70	572+20	LT	1									1	1	10	
	BOTH ENDS	572+20	572+70	LT	1									1		10	
LOCATION #3 SUB-TOTALS				2									50.00	2	1		
LOC #4	613+20	613+70	LT										50.00				
	EARTH EX	612+95	613+45	LT	1									1	1	10	
	BOTH ENDS	613+45	613+85	LT	1									1		10	
LOCATION #4 SUB-TOTALS				2									50.00	2	1		
LOC #5	615+10	622+10	RT										693.00				
	615+10	615+60	RT	1										1			
	615+60	621+80	RT						600.00						8		
	621+80	622+10	RT	1										1			
LOCATION #5 SUB-TOTALS				2				600.00					693.00	2	8		
LOC #6	641+79	645+00	LT/RT										221.00		4		
	641+26.75	641+78.75	NW QUAD	1										1			
	641+78.75	643+01.75	NW QUAD						125.00						2		
	643+01.75	643+15	NW QUAD			1											
	641+78.75	642+28.75	NE QUAD	1										1			
	642+26.75	643+01.75	NE QUAD						75.00						2		
	643+01.75	643+15	NE QUAD			1											
	ROCK EX	644+50	644+87	SW QUAD						1							10
ROCK EX	644+50	644+63.75	SE QUAD			1										10	
ROCK EX	644+63.75	644+88.25	SE QUAD	1										1		10	
LOCATION #6 SUB-TOTALS				3		3	1	200.00				221.00	3	8			
LOC #9	672+50	684+50	RT										1196.00				
	672+50	673+00	RT		1									1			
	673+00	684+00	RT						1100.00						14		
	684+00	684+50	RT	1										1			
LOCATION #9 SUB-TOTALS				1	1			1100.00				1196.00	2	14			
LOC #10	692+50	693+00	LT										50.00				
	EARTH EX	692+25	692+75	LT	1									1	1	10	
	BOTH ENDS	692+75	693+25	LT	1									1	1	10	
LOCATION #10 SUB-TOTALS				2									50.00	2	2		

FILE NAME *	USER NAME *	DESIGNED -	REVISED -
o:\p\work\p\1001\LAUGHLIN\10183217\0	loughlin	72059-shr-schedule.dgn	
PLOT SCALE = 1/20,000 ' / IN.	CHECKED -	REVISED -	
PLOT DATE = Mar-19-2010 11:34:45AM	DATE -	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
910	120 GUARDRAIL-1	HANCOCK	7	4
CONTRACT NO. 72059				
ILLINOIS FED. AID PROJECT				