

THERMOPLASTIC PAVEMENT MARKING - LINE 5"					FEET
EDGE LINE					
LOCATION	STATION	TO	STATION	LENGTH (FT)	
EB	9+15.52	TO	18+03.15	887.6	
EB	18+15.61	TO	25+67.9	752.3	
EB	27+15.91	TO	35+59.8	843.9	
WB	9+22.47	TO	18+03.15	880.7	
WB	18+15.61	TO	26+00.	784.4	
WB	27+46.97	TO	35+59.8	812.8	
TOTAL				4,148.9	

PAVEMENT MARKING REMOVAL					SQ FEET
EDGE LINE					
LOCATION	STATION	TO	STATION	SO FEET	
EB	9+15.52	TO	18+03.15	369.9	
EB	18+15.61	TO	25+67.9	313.5	
EB	27+15.91	TO	35+59.8	351.6	
WB	9+22.47	TO	18+03.15	367.0	
WB	18+15.61	TO	26+00.	326.8	
WB	27+46.97	TO	35+59.8	338.7	
TOTAL				2,067.4	

PAINT PAVEMENT MARKING - LINE 5"						FEET			
						WHITE	YELLOW		
						EDGE LINE	DBL SLD	SOLID	SKIP DASH
LOCATION	STATION	TO	STATION	LENGTH (FT)		LENGTH (FT)	LENGTH (FT)	LENGTH (FT)	
EB	35+59.8	TO	71+59.94	3,600.1					
EB	72+50.05	TO	77+42.54	492.5					
EB	78+27.77	TO	82+09.21	381.4					
EB	83+15.72	TO	98+19.86	1,504.1					
EB	98+99.87	TO	151+08.44	5,208.6					
EB	151+92.83	TO	173+21.46	2,128.6					
STATION EQUATION 173+21.46 BK = 173+25.13 AH									
EB	173+25.13	TO	205+60.93	3,235.8					
EB	206+31.78	TO	258+26.39	5,194.6					
EB	259+08.	TO	415+04.2	15,596.2					
EB	415+78.93	TO	468+44.05	5,265.1					
EB	469+12.11	TO	522+36.84	5,324.7					
EB	523+08.88	TO	572+82.63	4,973.8					
WB	35+59.8	TO	98+33.81	6,274.0					
WB	98+87.66	TO	173+21.46	7,433.8					
STATION EQUATION 173+21.46 BK = 173+25.13 AH									
WB	173+25.13	TO	191+79.61	1,854.5					
WB	192+67.34	TO	271+45.97	7,878.6					
WB	272+16.91	TO	311+20.14	3,903.2					
WB	311+87.51	TO	414+99.02	10,311.5					
WB	415+73.75	TO	522+24.79	10,651.0					
WB	522+95.49	TO	560+37.83	3,742.3					
WB	560+89.57	TO	572+82.63	1,193.1					
CL	35+59.8	TO	37+75.			430.4			
CL	37+75.	TO	173+21.46					3,386.6	
STATION EQUATION 173+21.46 BK = 173+25.13 AH									
CL	173+25.13	TO	184+75.					287.5	
CL	179+75.	TO	184+75.				500.0		
CL	184+75.	TO	187+75.			600.0			
CL	187+75.	TO	317+50.					3,243.8	
CL	187+75.	TO	195+25.				750.0		
CL	309+00.	TO	317+50.				850.0		
CL	317+50.	TO	322+00.			900.0			
CL	322+00.	TO	329+75.				775.0		
CL	322+00.	TO	366+00.					1,100.0	
CL	359+50.	TO	366+00.				650.0		
CL	366+00.	TO	367+50.			300.0			
CL	367+50.	TO	374+26.				676.0		
CL	367+50.	TO	399+75.					806.3	
CL	393+75.	TO	399+75.				600.0		
CL	399+75.	TO	405+75.			1,200.0			
CL	405+75.	TO	409+00.				325.0		
CL	405+75.	TO	425+00.					481.3	
CL	418+75.	TO	425+00.				625.0		
CL	425+00.	TO	428+00.			600.0			
CL	428+00.	TO	432+00.				400.0		
CL	428+00.	TO	471+00.					1,075.0	
CL	463+25.	TO	471+00.				775.0		
CL	471+00.	TO	473+50.			500.0			
CL	473+50.	TO	478+50.				500.0		
CL	473+50.	TO	517+00.					1,087.5	
CL	512+00.	TO	517+00.				500.0		
CL	517+00.	TO	521+50.			900.0			
CL	521+50.	TO	527+25.				575.0		
CL	521+50.	TO	532+00.					262.5	
CL	530+00.	TO	532+00.				200.0		
CL	532+00.	TO	548+25.			3,250.0			
CL	548+25.	TO	558+00.				975.0		
CL	548+25.	TO	572+82.6					614.4	
TOTAL						106,147.7	8,680.4	9,676.0	12,344.7

FILE NAME =	USER NAME = laughlinr1	DESIGNED -	REVISED -
e:\pwork\pwork\LAUGHLINRL\0182895\0672061-sh-t-schedule.dgn		DRAWN -	REVISED -
PLOT SCALE = 40.0000 ' / IN.		CHECKED -	REVISED -
PLOT DATE = Mar-25-2010 11:57:50AM		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
F.A.P. 315 (US 136)**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
315	(7,B) & (1)I-1, (2)I-2	MASON	34	14
CONTRACT NO. 72D61			ILLINOIS FED. AID PROJECT	