

			URBAN	90% FED 10% STATE
			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	SFTY-1B
20200100	EARTH EXCAVATION	CU YD	5.1	5.1
35300700	PORTLAND CEMENT CONCRETE BASE COURSE 12"	SQ YD	2.6	2.6
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	631.8	631.8
42400800	DETECTABLE WARNINGS	SQ FT	149.7	149.7
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	66	66
44000600	SIDEWALK REMOVAL	SQ FT	101.6	101.6
44003100	MEDIAN REMOVAL	SQ FT	152	152
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	55.8	55.8
67100100	MOBILIZATION	L SUM	1	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	10	10
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	143	143
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	10.4	10.4
78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	333.6	333.6
78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	78.1	78.1
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1