

Station Range			Length	Inside Shoulder	Outside Shoulder	2" HMA Surface Removal	2" HMA Shoulder	Bituminous Prime Coat	Shoulder Rumble Strips
			(ft)	(ft)	(ft)	(SY)	(T)	(T)	(ft)
Mainline									
81+00	204+42	EB	12,342.0	6	10	21,941	2,457	8.34	24,684
210+12	359+79	EB	14,966.9	6	10	26,608	2,980	10.11	29,934
0+00	1+10	EB	110.0	6	10	196	22	0.07	220
81+00	204+86	WB	12,386.0	6	10	22,020	2,466	8.37	24,772
210+63	359+79	WB	14,915.9	6	10	26,517	2,970	10.08	29,832
0+00	1+10	WB	110.0	6	10	196	22	0.07	220
Shoulders									
1+90	19+25	C	1,735.0	4	6	1,928	216	0.73	0
0+00	15+00	D	1,500.0	4	6	1,667	187	0.63	0

101,071 11,320 38 109,662

Pavement Marking

Mainline		Length	Edge	Center
		(ft)	(ft)	(ft)
81+00	359+79.8	27,879.8	111,519.2	13,939.9
0+00	1+10	110.0	440.0	55.0
Ramp C		1,735.0	3,470.0	
Ramp D		1,500.0	3,000.0	
			118,429.2	13,994.9
Total			132,424.1	