

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX, STANDARDS, & GENERAL NOTES
- 3 QUANTITIES
- 4 LOCATION MAP
- 5-6 SN 063-0006 DETAILS
- 7-8 SN 063-0005 DETAILS
- 9-10 SN 054-0004 DETAILS
- 11-12 SN 085-0026 DETAILS




STANDARDS

- 701001-02
- 701006-03
- 701101-02
- 701106-02
- 701201-03
- 701301-03
- 701901-01

GENERAL NOTES:

PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE A CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN THE SCOPE OF WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.

TOP SURFACE OF RIPRAP SHALL BE FLUSH WITH EXISTING GRADE. THE COST FOR REMOVAL AND DISPOSAL OF EARTH NECESSARY FOR RIPRAP INSTALLATION SHALL BE INCLUDED IN THE BID PRICE FOR STONE RIPRAP, CLASS A5 OR STONE DUMPED RIPRAP, CLASS A4.

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS DISTRICT 6		
EXAMINED	April 1	20 10
 ENGINEER OF OPERATIONS		
EXAMINED	APRIL 1	20 10
 ENGINEER OF PROGRAM IMPLEMENTATION		
EXAMINED	April 2	20 10
 ENGINEER OF PROGRAM DEVELOPMENT		

INDEX, STDS, & GENERAL NOTES  
VARIOUS ROUTES  
D6 RIPRAP PROTECTION 2010  
VARIOUS COUNTIES