

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

80/20 FED/ST

FAP 750

FAS 719

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	80/20 FED/ST		80/20 FED/ST	
				FAP 750	STRUCTURE SN. 026-2020 Y007	FAS 719	STRUCTURE S.N. 026-2019 Y007
				ROADWAY SECTION 114B-1(1) I000		ROADWAY SECTION 114B-1(2) I000	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	12	6		6	
** * 70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	2	1		1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5,624	1,557		4,067	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	743			743	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	725	425		300	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	725	425		300	
** 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	3,399	1,557		1,842	
** 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	5	2		3	
** * 78200410	GUARDRAIL MARKERS, TYPE A	EACH	10	10			
** * 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4			
78300100	PAVEMENT MARKING REMOVAL	SQ FT	528	179		349	
* Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	3	1		2	
* Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2		2	
* Z0030350	IMPACT ATTENUATORS, RELOCATE (NON- REDIRECTIVE), TEST LEVEL 3	EACH	4	2		2	
* Z0054505	ROCK FILL - REPLACEMENT	TON	247		106		141
* Z0076600	TRAINEES	HOUR	800	400		400	

* SEE SPECIAL PROVISIONS

** SPECIALTY ITEM

FILE NAME =	USER NAME = IE Consultants	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
G:\S08026-5XCADD Sheets\0774110-ilt-500.dgn		DRAWN -	REVISED -						* 114B-1(1) & 114B-1(2)	FAYETTE	54	7	
		PLOT SCALE = 10.0000" / IN.	CHECKED -		REVISED -	* F.A.P. RTE. 750, F.A.S. RTE. 719	CONTRACT NO. 74110						
		PLOT DATE = 9/29/2009	DATE -		REVISED -	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT						
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			