PAVING SCHEDULE			LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N90	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N90	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT MIX ASPHALT SHOULDERS	SHOULDER RUMBLE STRIPS	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT BASE COURSE, 10"
STATION	TO	STATION	FEET	FEET	FEET	SQ YD	GALLON	TON	TON	TON	TON	TON	FOOT	TON	SQ YD
118+87.50	TO	120+00.00	112.5	48.0	32.0	600.0	100.0	2.0		50.4	75.6	84.0	450.0	10.7	
120+00.00	TO	127+11.51	711.5	48.0	32.0	3,794.7	632.5	12.6		318.8	478.1	531.3	2,846.0	67.5	
127+11.51	TO	129+45.54	234.0	48.0	22.0	1,248.2	156.0	3.1		104.8	157.3	194.9	702.1	16.7	15.1
129+45.54	TO	130+63.26	117.7	48.0	12.0	627.8	78.5	1.6		52.7	79.1	79.9	235.4	5.6	281.0
130+63.26	TO	131+06.04	42.8	48.0	12.0	228.2	28.5	0.6		19.2	28.7	19.5	85.6	2.0	92.8
131+06.04	TO	131+50.00	44.0	48.0	12.0	234.5	29.3	0.6	2.0	19.7	29.5	18.9	87.9	2.1	90.0
131+50.00	TO	132+13.05	63.0	48.0	12.0	336.3	42.0	0.8	18.9	28.2	42.4	17.7	274.2	3.0	78.1
132+13.05	TO	135+75.47	362.4	0.0	0.0	0.0	0.0	0.0	4.4	0.0	0.0	0.0	0.0	0.0	29.0
135+75.47	TO	136+82.34	106.9	48.0	32.0	570.0	95.0	1.9	14.4	47.9	71.8	79.8	450.0	5.1	190.2
136+82.34	TO	140+71.07	388.7	48.0	32.0	2,073.2	345.5	6.9	1.5	174.2	261.2	290.3	1,554.9	18.4	792.4
140+71.07	TO	141+84.12	113.1	48.0	32.0	602.9	100.5	2.0	16.2	50.6	76.0	84.4	450.0	5.4	299.0
141+84.12	TO	143+20.27	136.2	0.0	0.0	0.0	0.0	0.0	1.2	0.0	0.0	0.0	0.0	0.0	71.0
143+20.27	TO	144+33.32	113.0	48.0	32.0	602.9	100.5	2.0	10.0	50.6	76.0	84.4	450.0	10.7	222.2
144+33.32	TO	162+35.00	1,801.7	48.0	32.0	9,609.0	1,601.5	32.0	7.7	807.2	1,210.7	1,345.3	6,988.2	171.0	545.0
162+35.00	TO	204+67.14	4,232.1	48.0	32.0	22,571.4	3,761.9	75.2		1,896.0	2,844.0	3,160.0	16,854.0	401.7	
204+67.14	TO	212+17.27	750.1	48.0	22.0	4,000.7	583.4	11.7		336.1	504.1	385.1	2,250.4	53.4	
212+17.27	TO	212+38.70	21.4	48.0	32.0	114.3	19.0	0.4		9.6	14.4	17.1	42.9	1.5	
212+38.70	TO	215+59.71	321.0	48.0	12.0	1,712.1	214.0	4.3		143.8	215.7	132.1	642.0	15.2	
215+59.71	TO	216+49.66	90.0	48.0	32.0	479.7	80.0	1.6		40.3	60.4	104.2	179.9	4.3	
216+49.66	TO	219+00.03	250.4	48.0	22.0	1,335.3	194.7	3.9		112.2	168.2	206.7	751.1	17.8	
219+00.03	TO	227+92.37	892.3	48.0	32.0	4,759.1	793.2	15.9		399.8	599.7	666.3	3,569.4	84.7	
227+92.37	TO	229+67.39	175.0	48.0	22.0	933.4	136.1	2.7		78.4	117.6	152.7	525.1	12.5	4.1
229+67.39	TO	231+33.02	165.6	48.0	12.0	883.4	110.4	2.2		74.2	111.3	113.2	331.3	11.8	398.6
231+33.02	TO	231+69.78	36.8	48.0	12.0	196.1	24.5	0.5		16.5	24.7	20.1	73.5	3.5	77.5
231+69.78	TO	231+95.62	25.8	48.0	12.0	137.8	17.2	0.3		11.6	17.4	7.2	51.7	2.5	52.6
231+95.62	TO	232+76.17	80.5	48.0	12.0	429.6	53.7	1.1	22.7	36.1	54.1	22.6	172.1	7.6	106.1
232+75.67	TO	236+22.50	346.8	0.0	0.0	0.0	0.0	0.0	1.0	0.0	0.0	0.0	0.0	0.0	9.5
236+22.50	TO	237+29.51	107.0	48.0	22.0	570.7	83.2	1.7	15.4	47.9	71.9	54.9	337.5	5.1	194.8
237+29.51	TO	241+49.81	420.3	48.0	22.0	2,241.6	326.9	6.5		188.3	282.4	215.8	1,260.9	39.9	278.0
241+49.81	TO	268+70.00	2,720.2	48.0	32.0	14,507.7	2,417.9	48.4		1,218.6	1,828.0	2,031.1	10,805.9	258.2	
268+70.00	TO	331+45.00	6,275.0	48.0	32.0	33,466.7	5,577.8	111.6		2,811.2	4,216.8	4,685.3	25,025.1	595.5	
331+45.00	TO	341+54.50	1,009.5	48.0	32.0	5,384.0	897.3	17.9	0.1	452.3	678.4	753.8	3,962.8	95.8	
341+54.50	TO	342+67.00	112.5	48.0	32.0	600.0	100.0	2.0	17.9	50.4	75.6	84.0	374.8	10.7	
342+67.00	TO	350+22.00	755.0	0.0	0.0	0.0	0.0	0.0	13.0	0.0	0.0	0.0	0.0	0.0	
350+22.00	TO	351+34.50	112.5	48.0	32.0	600.0	100.0	2.0	5.0	50.4	75.6	84.0	450.0	10.7	
351+34.50	TO	367+40.00	1,605.5	48.0	32.0	8,562.7	1,427.1	28.5		719.3	1,078.9	1,198.8	6,422.0	152.4	
SHEET TOTALS			24,853			124,014	20,228	405	151	10,417	15,626	16,925	88,657	2,103	3,827