

PAVING SCHEDULE (Cont' d)			LENGTH	PAVEMENT WIDTH	SHOULDER WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), N90	POLYMERIZED HOT MIX ASPHALT SURFACE COURSE, MIX "D", N90	POLYMERIZED HOT MIX ASPHALT BINDER COURSE, IL-19.0, N90	HOT MIX ASPHALT SHOULDERS	SHOULDER RUMBLE STRIPS	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT BASE COURSE, 10"
STATION	TO	STATION	FEET	FEET	FEET	SQ YD	GALLON	TON	TON	TON	TON	TON	FOOT	TON	SQ YD
Ramp B IL 48															
401+75.68	TO	402+83.44	107.8	*Var Table	6.0	232.5	23.2	0.5		13.2	19.7	15.9		0.0	
402+83.44	TO	403+22.46	39.0	*Var Table	6.0	99.6	10.0	0.2		6.2	9.3	5.5		0.0	
403+22.46	TO	406+62.40	339.9	16.0	6.0	831.0	83.1	1.7		50.8	76.1	47.6		0.0	
406+62.40	TO	423+94.12	1,731.7	16.0	10.0	5,002.7	500.3	10.0		258.6	387.9	404.1		82.2	
423+94.12	TO	424+26.78		*Var Table	10.0	98.0	9.8	0.0		5.2	7.8	7.6		1.5	
424+26.78	TO	425+01.78	75.0	*Var Table	*Var Table	672.9	67.3	1.3		29.5	44.2	67.6		3.6	
Ramp C IL 48															
500+35.00	TO	501+10.00	75.0	*Var Table	*Var Table	501.3	50.1	1.0		26.4	39.6	39.3		3.6	
501+10.00	TO	501+38.47	28.5	*Var Table	10.0	84.6	8.5	0.2		4.5	6.7	6.6		1.4	
501+38.47	TO	513+15.85	1,177.4	16.0	10.0	3,401.3	340.1	6.8		175.8	263.7	274.7		55.9	
501+38.47	TO	515+12.69	1,374.2	16.0	6.0	3,359.2	335.9	6.7		205.2	307.8	192.4		0.0	71.7
515+12.69	TO	516+18.17	105.5	*Var Table	6.0	284.4	28.4	0.6		17.7	26.5	15.5		0.0	
516+18.17	TO	519+59.42		0.0	0.0	0.0	0.0	0.0		0.0	0.0	0.0		0.0	
519+59.42	TO	524+96.33	536.9	*Var Table	6.0	738.1	73.8	1.5		31.9	47.9	75.2		0.0	
Ramp D IL 48															
599+81.00	TO	603+21.61	340.6	*Var Table	6.0	568.6	56.9	1.1		28.7	43.0	47.7		0.0	
603+21.61	TO	606+62.40	340.8	16.0	6.0	833.0	83.3	1.7		50.9	76.3	47.7		0.0	
606+62.40	TO	622+50.78	1,588.4	16.0	10.0	4,588.7	458.9	9.2		237.2	355.8	370.6		75.4	
622+50.78	TO	622+85.52	34.7	*Var Table	10.0	38.6	3.9	0.1		0.0	0.0	8.1		1.6	
622+85.52	TO	623+60.52	75.0	*Var Table	*Var Table	557.3	55.7	1.1		30.5	45.8	40.7		3.6	
MEDIAN CROSS-OVERS															
162+34.00				*Var Table	*Var Table					28.1				4.2	334.9
268+70.00				*Var Table	*Var Table					28.1				4.2	334.8
331+45.00				*Var Table	*Var Table					28.1				4.2	334.6
SHEET TOTALS			7,970			21,892	2,189	44	0	1,257	1,758	1,667	0	241	1,076
PROJECT TOTALS			44,697			476,488	25,631	510	151	13,401	19,975	21,021	88,657	2,728	5,018