

DELINEATOR SCHEDULE					
LOCATION		FACH	LOCATION		FACH
115+39.98	LT	1.0	227+40.00	RT	1.0
117+39.99	RT/LT	2.0	251+40.00	RT/LT	2.0
118+89.99	RT/LT	2.0	255+40.00	RT/LT	2.0
120+39.99	RT/LT	2.0	259+40.00	RT/LT	2.0
121+89.99	RT/LT	2.0	263+40.00	RT/LT	2.0
123+39.99	RT/LT	2.0	267+40.00	RT/LT	2.0
124+89.99	RT/LT	2.0	271+40.00	RT/LT	2.0
126+39.99	RT/LT	2.0	275+40.00	RT/LT	2.0
127+89.99	RT	1.0	279+40.00	RT/LT	2.0
129+39.99	RT	1.0	283+40.00	RT/LT	2.0
147+40.00	RT/LT	2.0	287+40.00	RT/LT	2.0
151+40.00	RT/LT	2.0	291+40.00	RT/LT	2.0
155+40.00	RT/LT	2.0	295+40.00	RT/LT	2.0
159+40.00	RT/LT	2.0	299+40.00	RT/LT	2.0
163+40.00	RT/LT	2.0	303+40.00	RT/LT	2.0
167+40.00	RT/LT	2.0	307+40.00	RT/LT	2.0
171+40.00	RT/LT	2.0	311+40.00	RT	1.0
175+40.00	RT/LT	2.0	315+40.00	RT/LT	2.0
179+40.00	RT/LT	2.0	319+40.00	RT/LT	2.0
183+40.00	RT/LT	2.0	323+40.00	RT/LT	2.0
187+40.00	RT/LT	2.0	327+40.00	RT/LT	2.0
191+40.00	RT/LT	2.0	331+41.00	RT/LT	2.0
195+40.00	RT/LT	2.0	335+40.00	RT/LT	2.0
199+40.00	RT/LT	2.0	339+40.00	RT/LT	2.0
203+40.00	RT/LT	2.0	351+40.00	RT/LT	2.0
207+40.00	RT	1.0	355+40.00	RT/LT	2.0
211+40.00	RT	1.0	359+40.00	RT/LT	2.0
219+40.00	LT	1.0	363+40.00	RT/LT	2.0
223+40.00	RT/LT	2.0	367+40.00	RT/LT	2.0
COLUMN TOTAL		52.0	COLUMN TOTAL		56.0

DELINEATOR SCHEDULE					
LOCATION		FACH	LOCATION		FACH
US 51/BUS. 51 RAMP A					
205+40.56	TO	209+40.56	RT		5
210+40.56	TO	216+40.56	RT/LT		14
217+40.56	TO	218+40.56	RT		2
US 51/BUS. 51 RAMP B					
307+00.00	TO	308+00.00	LT		2
309+00.00	TO	310+00.00	RT/LT		4
311+00.00	TO	317+00.00	LT		7
US 51/BUS. 51 RAMP C					
706+00.00	TO	713+00.00	RT/LT		16
714+00.00	TO	715+00.00	LT		2
US 51/BUS. 51 RAMP D					
895+05.88	TO	901+05.88	RT		6
902+05.88	TO	911+05.88	RT/LT		18
912+05.88	TO	919+05.88	RT		8
US 51/IL 48 RAMP A					
307+73.82	TO	313+73.82	RT		7
314+73.82	TO	320+73.82	RT/LT		14
321+73.82	TO	332+73.82	RT		12
US 51/IL 48 RAMP B					
402+00.00	TO	406+00.00	RT		5
407+00.00	TO	408+00.00	RT/LT		4
409+00.00	TO	418+00.00	LT		10
US 51/IL 48 RAMP C					
504+03.75	TO	513+03.75	RT/LT		20
514+03.75			RT		1
US 51/IL 48 RAMP D					
600+00.00	TO	606+00.00	RT		7
607+00.00	TO	614+00.00	RT/LT		16
615+00.00	TO	620+00.00	RT		6
COLUMN TOTAL					186
PROJECT TOTAL					294.0

TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION			LENGTH	
			FT.	
NB PL WORK AREA SN. 058-0102				
129+81.20	TO	131+32.50	151	12: 1 TAPER
131+32.50	TO	136+77.10	545	
SB PL WORK AREA SN. 058-0101				
131+08.30	TO	136+56.20	548	
136+56.20	TO	138+09.20	153	12: 1 TAPER
NB PL WORK AREA SN. 058-0104				
139+28.60	TO	140+81.60	153	12: 1 TAPER
140+81.60	TO	144+74.20	393	
SB PL WORK AREA SN. 058-0105				
140+28.80	TO	144+22.90	394	
144+22.90	TO	145+75.90	153	12: 1 TAPER
NB PL WORK AREA SN. 058-0109				
230+27.70	TO	231+80.70	153	12: 1 TAPER
231+80.70	TO	237+12.70	532	
SB PL WORK AREA SN. 058-0108				
231+86.20	TO	237+18.30	532	
237+18.30	TO	238+71.20	153	12: 1 TAPER
TOTAL =			3,860	

RELOCATE TEMPORARY CONCRETE BARRIER SCHEDULE

LOCATION			LENGTH	
			FT.	
NB DL WORK AREA SN. 058-0102				
130+63.00	TO	131+32.40	69	12: 1 TAPER
131+32.40	TO	136+77.10	545	
SB DL WORK AREA SN. 058-0101				
131+08.30	TO	136+56.20	548	
136+56.20	TO	138+09.20	153	12: 1 TAPER
NB DL WORK AREA SN. 058-0104				
139+28.60	TO	140+81.50	153	12: 1 TAPER
140+81.50	TO	144+75.70	394	
SB DL WORK AREA SN. 058-0105				
140+28.80	TO	144+22.80	394	
144+22.80	TO	145+75.90	153	12: 1 TAPER
NB DL WORK AREA SN. 058-0109				
231+13.00	TO	231+80.60	68	12: 1 TAPER
231+80.60	TO	237+12.70	532	
SB DL WORK AREA SN. 058-0108				
231+86.30	TO	237+18.30	532	
237+18.30	TO	238+71.30	153	12: 1 TAPER
TOTAL =			3,694	

EARTHWORK SCHEDULE

Location	Earth Excavation		Earthwork Balance	
	Earth Excavation	Adj. for Shrinkage	Embankment	Waste (+)/Shortage (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
128+31.85 TO 132+24.13 (NB MEDIAN SN 058-0101)			75.4	-75.4
135+91.66 TO 139+59.27 (SB MEDIAN SN 058-0102)			70.7	-70.7
137+83.34 TO 141+67.71 (NB MEDIAN SN 058-0104)			73.9	-73.9
143+37.08 TO 147+21.46 (SB MEDIAN SN 058-0105)			73.9	-73.9
228+65.62 TO 232+45.57 (NB MEDIAN SN 058-0109)			73.0	-73.0
236+30.87 TO 240+16.57 (SB MEDIAN SN 058-0108)			74.1	-74.1
309+75.00 TO 315+25.00 (MEDIAN IMPACT ATTEN.)	9.0	6.8	969.0	-962.3
PROJECT TOTAL	9.0	6.8	1410.0	-1,403