PAVEMENT MARKING SCHEDULE (Cont'd)			LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMNT MARKING-LINE 4" (YELLOW)	TEMPORARY PAVEMNT MARKING-LINE 4" (WHITE)	TEMPORARY PAVEMNT MARKING-LINE 6"	TEMPORARY PAVEMNT MARKING-LINE 8"	TEMPORARY PAVEMNT MARKING-LINE 12"	TEMPORARY PAVEMNT MARKING-LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	PREFORMED PLASTIC PAVEMENT MARKING, TYPEB-INLAID-6"	URETHANE PAVEMNT MARKING-LINE 4" (YELLOW)	URETHANE PAVEMNT MARKING-LINE 4" (WHITE)	URETHANE PAVEMNT MARKING-LINE 6"	URETHANE PAVEMNT MARKING-LINE 8"	URETHANE PAVEMNT MARKING-LINE 12"	URETHANE PAVEMNT MARKING-LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER (CRYSTAL)	RAISED REFLECTIVE PAVEMENT MARKER (AMBER)
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
RAMP B BUS. 51																				
300+00.00	TO	301+85.81	185.8			185.8					61.9			185.8					10.0	
301+85.81	TO	302+77.22	91.4			91.4					30.5			91.4					7.0	
302+77.22	TO	307+11.36	434.1			434.1		437.2			436.2			434.1		437.2			45.0	1.0
307+11.36	TO	316+55.93	944.6		991.0	944.6					645.2		991.0	944.6						25.0
316+55.93	TO	320+79.65	423.7		423.7	423.7					282.5		423.7	423.7						
320+79.65	TO	321+11.38	31.7		31.7	32.2					21.3		31.7	32.2						
321+11.38	TO	321+86.38	75.0		70.0	147.3		163.6	56.2	36.0	309.7		70.0	147.3		163.6	56.2	36.0		
RAMP C BUS. 51																				
700+36.24	TO	701+11.24	75.0		80.7	135.7					72.1		80.7	135.7						
701+11.24	TO	701+51.09	39.8		39.9	40.2					26.7		39.9	40.2						
701+51.09	TO	706+00.00	448.9		448.9	448.9					299.3		448.9	448.9						
706+00.00	TO	714+87.62	887.6		1,014.0	887.6					633.9		1,014.0	887.6						
714+87.62	TO	716+06.15	118.5			118.5		118.6			118.6			118.5		118.6				
716+06.15	TO	720+42.88	436.7			436.7	109.2				182.0			436.7	109.2					
720+42.88	TO	726+92.82	649.9			649.9					216.6			649.9						
RAMP D BUS. 51																				
901+68.27	TO	902+18.27	50.0			50.0		50.0			50.0			50.0		50.0			4.0	1.0
902+18.27	TO	923+46.17	2,127.9		2,121.2	2,127.9					1,416.4		2,121.2	2,127.9					24.0	23.0
923+46.17	TO	923+72.46	26.3		25.2	25.1					16.7		25.2	25.1						
923+72.46	TO	924+47.46	75.0		71.9	154.9		169.8	55.8	36.0	316.6		71.9	154.9		169.8	55.8	36.0		
RAMP A IL 48																				
300+35.00	TO	301+10.00	75.0		75.9	141.9					72.6		75.9	141.9						
301+10.00	TO	301+38.47	28.5		28.5	28.6					19.0		28.5	28.6						
301+38.47	TO	320+49.57	1,911.1		1,906.2	1,911.1					1,272.4		1,906.2	1,911.1						
320+49.57	TO	321+68.30	118.7			118.7		121.2			120.4			118.7		121.2				
321+68.30	TO	326+28.49	460.2			460.2	460.2				306.8			460.2	460.2					
326+28.49	TO	332+78.35	649.9			649.9					216.6			649.9						
SHEET TOTALS			10,366	0	7,329	10,645	569	1,060	112	72	7,144	0	7,329	10,645	569	1,060	112	72	90	50