

PAVEMENT MARKING SCHEDULE (Cont'd)		LENGTH	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING-LINE 4" (YELLOW)	TEMPORARY PAVEMENT MARKING-LINE 4" (WHITE)	TEMPORARY PAVEMENT MARKING-LINE 6"	TEMPORARY PAVEMENT MARKING-LINE 8"	TEMPORARY PAVEMENT MARKING-LINE 12"	TEMPORARY PAVEMENT MARKING-LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	PERFORMED PLASTIC PAVEMENT MARKING, TYPEB-INLAID-6"	URETHANE PAVEMENT MARKING-LINE 4" (YELLOW)	URETHANE PAVEMENT MARKING-LINE 4" (WHITE)	URETHANE PAVEMENT MARKING-LINE 6"	URETHANE PAVEMENT MARKING-LINE 8"	URETHANE PAVEMENT MARKING-LINE 12"	URETHANE PAVEMENT MARKING-LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER (CRYSTAL)	RAISED REFLECTIVE PAVEMENT MARKER (AMBER)
STATION TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	EACH	EACH
RAMP B IL 48																			
400+00.00	TO 401+69.69	169.7			169.7					56.6			169.7					9.0	
401+69.69	TO 402+77.13	107.4			107.4					35.8			107.4					8.0	
402+77.13	TO 407+11.37	434.2			434.2		435.2			434.9			434.2		435.2			45.0	1.0
407+11.37	TO 417+62.95	1,051.6		1100.8	1051.6					717.4		1100.8	1051.6						27.0
417+62.95	TO 423+94.12	631.2		631.2	631.2					420.8		631.2	631.2						
423+94.12	TO 424+26.78	32.7		32.7	32.8					21.8		32.7	32.8						
424+26.78	TO 425+01.78	75.0		79.3	143.9		163.6	56.2	36.0	311.7		79.3	143.9		163.6	56.2	36.0		
RAMP C IL 48																			
500+35.00	TO 501+10.00	75.0		75.9	141.9					72.6		75.9	141.9						
501+10.00	TO 501+38.47	28.5		28.5	28.6					19.0		28.5	28.6						
501+38.47	TO 504+03.76	265.3		265.3	265.3					176.9		265.3	265.3						
504+03.76	TO 512+66.88	863.1		908.5	863.1					590.5		908.5	863.1						
512+66.88	TO 513+84.34	117.5			117.5		119.8			119.0			117.5		119.8				
513+84.34	TO 518+47.38	463.0			463.0	463.0				308.7			463.0	463.0					
518+47.38	TO 524+96.33	649.0			649.0					216.3			649.0						
RAMP D IL 48																			
599+81.00	TO 602+77.06	296.1			296.1					98.7			296.1					17.0	
602+77.06	TO 607+11.37	434.3			434.3		435.3			435.0			434.3		435.3			45.0	1.0
607+11.37	TO 622+50.78	1,539.4		1538.4	1539.4					1025.9		1538.4	1539.4						16.0
622+50.78	TO 622+85.52	34.7		34.7	34.9					23.2		34.7	34.9						
622+85.52	TO 623+60.52	75.0		79.3	147.7		169.8	55.8	36.0	316.7		79.3	147.7		169.8	55.8	36.0		
SHEET TOTALS		7,343	0	4,774	7,552	463	1,324	112	72	5,401	0	4,774	7,552	463	1,324	112	72	124	45
PROJECT TOTALS		7,343	10,603	61,512	61,951	1,032	3,743	224	144	45,630	11,684	61,512	61,951	1,032	3,743	224	144	1,378	95