SHORT TERM/TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION			X0325842	X0325775		X0325837		X0325841	70300100	70301000
STATION	TO	STATION	WET REFLECTIVE TEMPORARY TAPE TYPE III LTR & SYM (SQ FT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, LINE 4" WHITE (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, LINE 4" YELLOW (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, LINE 6" WHITE (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, LINE 6" YELLOW (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, LINE 24" (FOOT)	SHORT TERM PAVEMENT MARKING WHITE (FOOT)	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
SHORT TERM										
1223+00	TO	1230+00							230	77
1230+20	TO	1241+20							200	67
TEMPORARY										
1223+00	TO	1230+00	83	140		310	106	73		484
1230+00	TO	1233+00		255	261	140				242
1233+00	TO	1239+00		600	600	150				475
1239+00	TO	1241+20		221	221	60				178
SUBTOTAL				1216	1082	660	106			
TOTAL			83	2298		766		73	430	1523

TRAFFIC CONTROL SCHEDULE

LOCATION			70301000	70400100	70400200	78300100	X0325774	X0325775		XX006198
STATION	TO	STATION	WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	PAVEMENT MARKING REMOVAL (SQ FT)	RELOCATE TEMPORARY IMPACT ATTENUATOR (EACH)	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH WHITE (FOOT)	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH YELLOW (FOOT)	IMPACT ATTENUATOR, TEMPORARY (NON-REDIR) (EACH)
US 51 BUSINESS - PRE-STAGE I										
1230+20	TO	1241+20				176				
US 51 BUSINESS STAGE I										
1223+24	TO	1224+98	58			15		348		
1230+20	TO	1241+20	34					1355	1100	
1232+18	TO	1240+29		811						1
US 51 BUSINESS STAGE II										
1223+24	TO	1224+98	58					522		
1230+20	TO	1241+20	444					1100	2200	
1231+82	TO	1241+26		1077	811		1			
US 51 BUSINESS STAGE III										
1223+24	TO	1224+98	174					174		
1230+39	TO	1241+20						1352		
1232+14	TO	1241+26			912		1			
1232+75	TO	1239+34	495							
SUB-TOTALS								4851	3300	
TOTAL			1263	1888	1723	191	2	8151		1

STORM SEWER STRUCTURE SCHEDULE

STRUCTURE NUMBER	CENTERLINE STATION	OFFSET	20800150 TRENCH BACKFILL (CU YD)	28000500 INLET AND PIPE PROTECTION (EACH)	60218500 MANHOLES, TYPE A 4 DIA T3F&G (FOOT)	60500060 REMOVING INLETS (FOOT)
US 51 BUSINESS						
B	1230+45.00	20.29' RT	4	1	1	1
C	1232+00.00	20.12' RT	4	1	1	1
E	1232+00.00	20.12' LT	3	1	1	1
TOTAL			11	3	3	3

PAVEMENT MARKING SCHEDULE

LOCATION			78008300	78008310		78008330		78008370	78100100	78100105
STATION	TO	STATION	POLYUREA PVT MARKING TYPE II LTR & SYM (SQ FT)	WHITE POLYUREA PVT MARKING TYPE II LINE 4" (FOOT)	YELLOW POLYUREA PVT MARKING TYPE II LINE 4" (FOOT)	WHITE POLYUREA PVT MARKING TYPE II LINE 6" (FOOT)	YELLOW POLYUREA PVT MARKING TYPE II LINE 6" (FOOT)	POLYUREA PVT MARKING TYPE II LINE 24" (FOOT)	RAISED REFLECTIVE PAVEMENT MARKER (EACH)	RAISED REFLECTIVE PVT MKR (BRIDGE) (EACH)
US 51 BUSINESS										
1223+00	TO	1230+00	83	140		310	106	73	18	
1230+00	TO	1233+00		255	261	140			8	
1233+00	TO	1239+00		600	600	150				16
1239+00	TO	1241+20.24		221	221	60			6	
SUB-TOTAL				1216	1082	660	106			
TOTAL			83	2298		766		73	32	16

PAVEMENT SCHEDULE

LOCATION			OFFSET	31100500 SUB-BASE GRANULAR MATL, TY A, 6" (SQ YD)	35400500 PCC BASE CSE WIDENING, 10" (SQ YD)	40600100 BITUMINOUS MATERIALS (PR CT) (GALLON)	40603240 POLYMERIZED HMA BINDER COURSE, IL-19.0, N90 (TON)	40603545 POLYMERIZED HMA SURFACE COURSE, MIX "D", N90 (TON)	420001420 BRIDGE APPROACH PAVEMENT CONN (PCC) (SQ YD)	60605000 COMB CC&G, TY B-6.24 (FOOT)
STATION	TO	STATION	RT/LT							
US 51 BUSINESS										
1230+21	TO	1230+39				10		7		
1230+21	TO	1230+39	LT	10	3					
1230+21	TO	1232+83	LT							262
1230+39	TO	1232+81	RT							242
1230+39	TO	1232+74.68				107		86		
1230+39	TO	1232+74.68	RT	131	64					
1230+39	TO	1232+74.68	LT	131	64					
1231+74.92	TO	1232+74.68	RT/LT				43			
1232+74.68	TO	1232+81.92		37					33	
1239+14	TO	1241+20.24	RT							206
1239+20.54	TO	1239+33.54		67					59	
1239+27	TO	1241+20.24	LT							193
1239+33.54	TO	1240+35.28	LT	68	28					
1239+33.54	TO	1240+35.28	RT	68	28					
1239+33.54	TO	1240+35.28				46	43	43		
1240+35.24	TO	1241+20.24	RT	51	17					
1240+35.24	TO	1241+20.24	LT	51	17					
1240+35.28	TO	1241+20.24				36		25		
FRANKLIN STREET										
1230+21	TO	1230+39	RT							17
			TOTAL	614	221	199	86	161	92	920

GUARDRAIL SCHEDULE

LOCATION			OFFSET	63000001 STEEL BEAM GUARDRAIL, TYPE A 6 FT POSTS (FOOT)	63100045 TRAFFIC BARRIER TERMINAL, TYPE 2 (EACH)	63100070 TRAFFIC BARRIER TERMINAL, TYPE 5 (EACH)	63200310 GUARDRAIL REMOVAL (FOOT)
STATION	TO	STATION	RT/LT				
US 51 BUSINESS							
1238+99	TO	1239+14	RT			1	
1239+14	TO	1241+89	RT	275			
1241+89	TO	1242+04	RT		1		
1240+35	TO	1240+50	LT			1	
1240+50	TO	1241+87	LT	138			
1241+87	TO	1242+02	LT		1		
PIER #5 (NSRR TRACKS)							
SOUTH			RT/LT				60
PIER #6 (NSRR TRACKS)							
NORTH			LT	30			30
PIER #8 (WABASH AVE)							
SOUTH			RT/LT				135
			TOTAL	443	2	2	225

SEEDING SCHEDULE

LOCATION			OFFSET	25001000 SEEDING, CLASS 2 (SPECIAL) (ACRE)
STATION	TO	STATION	RT/LT	
US 51 BUSINESS				
1230+20.87	TO	1230+45.87	LT	0.01
1238+99	TO	1242+04	RT	0.14
1240+99	TO	1242+02	LT	0.05
			TOTAL	0.20

PAVEMENT REMOVAL SCHEDULE

LOCATION			OFFSET	44000100 PAVEMENT REMOVAL (SQ YD)	44000154 HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/4" (SQ YD)	44000500 COMB. CURB & GUTTER REMOVAL (FOOT)
STATION	TO	STATION	RT/LT			
US 51 BUSINESS						
1230+39	TO	1233+10.42	RT			271
1230+21	TO	1233+10.42	LT			289
1230+21	TO	1232+74.68	RT/LT	123	1015	
1232+74.68	TO	1233+10.42	RT/LT	168		
1238+91.35	TO	1241+20.24	RT			229
1238+91.35	TO	1241+20.24	LT			229
1238+91.35	TO	1239+33.54	RT/LT	184		
1239+33.54	TO	1241+20.24	RT/LT	28	747	
FRANKLIN STREET						
1230+21	TO	1230+39	RT		24	17
			TOTAL	503	1786	1035

FILE NAME = K:\CH\IE\2007\07.07\cad\Plans\Schedule of Quantities.dgn

Foth
Foth Infrastructure & Environment, LLC

USER NAME = maj	DESIGNED - JLF	REVISED -	
	DRAWN - JDK	REVISED -	
PLOT SCALE = 1.0000 ' / IN.	CHECKED - DAR/TLO	REVISED -	
PLOT DATE = 4/9/2010	DATE - 09/24/2009	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
710	(50Z-VB) BR	MACON	79	9
		CONTRACT NO. 74215		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		