

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	80% FED. 20% STATE	ROADWAY	STRUCTURE		
			TOTAL QUANTITY	I000	X071-2A		
50300300	PROTECTIVE COAT	SQ YD	899		899		
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	1,064.5		1,064.5		
50500505	STUD SHEAR CONNECTORS	EACH	432		432		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	112,820		112,820		
50800515	BAR SPLICERS	EACH	1,035		1,035		
51201400	FURNISHING STEEL PILES HP10X42	FOOT	1,624		1,624		
51201500	FURNISHING STEEL PILES HP10X57	FOOT	1,276		1,276		
51202305	DRIVING PILES	FOOT	2,900		2,900		
51203400	TEST PILE STEEL HP10X42	EACH	2		2		
51203500	TEST PILE STEEL HP10X57	EACH	2		2		
51500100	NAME PLATES	EACH	1		1		
52000110	PREFORMED JOINT STRIP SEAL	FOOT	98		98		
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	24		24		
52100520	ANCHOR BOLTS, 1"	EACH	52		52		
542D0220	PIPE CULVERTS, CLASS D, TYPE 1, 15"	FOOT	40	40			
542D0235	PIPE CULVERTS, CLASS D, TYPE 1, 30"	FOOT	194	194			
* 54215547	METAL END SECTIONS 12"	EACH	4	4			
* 54215550	METAL END SECTIONS 15"	EACH	2	2			
* 54215565	METAL END SECTIONS 30"	EACH	4	4			

* SEE SPECIAL PROVISIONS
RR quantity items

FILE NAME = G:\S8826-7\CADD Sheets\0774236-sh1-500.dgn	USER NAME = IE Consultants	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
PLOT SCALE = 10.0000' / IN.	CHECKED -	REVISED -	REVISED -						116	(112BR)B	CUMBERLAND	72	6
PLOT DATE = 8/13/2009	DATE -	REVISED -	REVISED -		CONTRACT NO. 74236				ILLINOIS FED. AID PROJECT				
					SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.			