

SIGN SCHEDULE				
STA	OFFSET	LT / RT	TYPE	X0321866 REMOVE, STORE AND RE-ERECT SIGN PANEL (SQ FT)
370+75	23'	RT	STREET	3
370+84	45'	RT	STOP	6.25
371+44	56'	LT	PRIVATE	9
371+79	48'	RT	STOP	6.25
<b>TOTAL</b>				<b>24.50</b>
<b>USE</b>				<b>25</b>

EROSION CONTROL SCHEDULE					
STA	OFFSET	LT / RT	28000300 TEMPORARY DITCH CHECKS (EACH)	28000400 PERIMETER EROSION BARRIER (FOOT)	28000500 INLET AND PIPE PROTECTION (EACH)
371+35 TO 373+50				215	
371+09	50'	RT			1
374+90	67'	LT	1		
375+30	65'	LT	1		
375+95	64'	RT	1		
376+50	65'	RT	1		
379+42	25'	LT			1
379+69	55'	RT			1
<b>TOTAL</b>			<b>4</b>	<b>215</b>	<b>3</b>

TREE REMOVAL SCHEDULE					
STA	TO	STA	LT / RT	AREA FROM CAD (SQ FT)	20100500 TREE REMOVAL (ACRES)
373+25		375+00	LT	4,334	0.10
375+30		378+60	LT	4,232	0.10
<b>TOTALS</b>					<b>0.2</b>

RIGHT OF WAY MARKER SCHEDULE			
STA	OFFSET	LT / RT	66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS (EACH)
370+40.00	45'	RT	1
371+29.65	45'	LT	1
371+62.38	90'	RT	1
372+23.21	90'	RT	1
373+00.00	100'	LT	1
376+00.00	100'	LT	1
378+50.00	45'	LT	1
379+50.00	90'	RT	1
380+50.00	45'	RT	1
<b>TOTAL</b>			<b>9</b>

TEMPORARY CONCRETE BARRIER SCHEDULE									
STA.	OFFSET	TO	STA.	OFFSET	LOCATION	70400100 TEMPORARY CONCRETE BARRIER (FOOT)	70400200 RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	Z0030250 IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	Z0030350 IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
372+39	4		373+36	-4	STAGE 1	98			
373+36	-4		378+07	-4	STAGE 1	471			
378+07	-4		379+04	4	STAGE 1	98			
372+30					STAGE 1			1	
379+13					STAGE 1			1	
372+29	-4		373+13	3	STAGE 2		85		
373+13	3		377+96	3	STAGE 2		483		
377+96	3		378+80	-4	STAGE 2		85		
QUANTITY NOT NEEDED FROM STAGE 1							12.5		
372+20					STAGE 2				1
378+89					STAGE 2				1
<b>TOTALS</b>						<b>667.0</b>	<b>666</b>	<b>2</b>	<b>2</b>
<b>USE</b>						<b>675.0</b>	<b>675.0</b>	<b>2</b>	<b>2</b>

EARTHWORK			
20200100 EARTH EXCAVATION [CUT] (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) (CU YD)	EMBANKMENT [FILL] (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
3940	2955	5590	-2635
<b>3940</b>	<b>2955</b>	<b>5590</b>	<b>-2635</b>