

SUMMARY OF QUANTITIES (Cont'd)			100% STATE	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	RURAL 1000	URBAN 1000	025-0087 SFTY-2A	025-0079 SFTY-2A	025-0086 SFTY-2A
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10288	7168	3120			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	31		31			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	82559	59560	22999			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	125		125			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	594		594			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	857	597	260			
70400100	TEMPORARY CONCRETE BARRIER	FOOT	425			425		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	337			337		
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	31		31			
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	17686		17686			
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	125		125			
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	594		594			
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	64873	59561	5312			
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	503	255	248			
80500100	SERVICE INSTALLATION, TYPE A	EACH	1	1				
81012600	CONDUIT IN TRENCH, 2" DIA., PVC	FOOT	2963	2963				
81013000	CONDUIT IN TRENCH, 4" DIA., PVC	FOOT	52	52				
81021550	CONDUIT, AUGERED 2" DIA., PVC	FOOT	186	186				
81021590	CONDUIT, AUGERED 4" DIA., PVC	FOOT	84	84				
81100400	CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., GALVANIZED STEEL	FOOT	88	88				
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	195	195				
81500100	GULFBOX JUNCTION	EACH	5	5				
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	9964	9964				
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	42				42	
X0323077	SILICONE JOINT SEALER, 2 3/4"	FOOT	84					84
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	25			25		
XZ193500	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 2 1/4"	SO YD	753			753		
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SO YD	753			753		
Z0025500	FURNISHING AND INSTALLING PROPERTY MARKERS	EACH	21	9	12			
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2			2		
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	1			1		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2			2		

\*

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = swartzrv	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pw_work\PWIDOT\SWARTZRV\dms54414\sh	soq_74317.dgn	DRAWN -	REVISED -		SCALE: NA	SHEET NO. 2 OF 2 SHEETS	STA.	TO STA.	2796	(L)KRS-2	EFFINGHAM	58	4
	PLOT SCALE = 40,0000' / IN.	CHECKED -	REVISED -					<b>CONTRACT NO. 74317</b>					
	PLOT DATE = 3/18/2010	DATE -	REVISED -					ILLINOIS FED. AID PROJECT					