

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		018-0025 SFTY-2A	
35300400	PORTLAND CEMENT CONCRETE BASE COURSE 9"	SQ YD	74	74	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	199	199	
44001114	HOT-MIX ASPHALT SURFACE REMOVAL (ASBESTOS)	SQ YD	978	978	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	379	379	
50102400	CONCRETE REMOVAL	CU YD	22.3	22.3	
50157300	PROTECTIVE SHIELD	SQ YD	529	529	
50300100	FLOOR DRAINS	EACH	17	17	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	24.7	24.7	
50300260	BRIDGE DECK GROOVING	SQ YD	873	873	
50300300	PROTECTIVE COAT	SQ YD	960	960	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1920	1920	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	18	18	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2890	2890	
50800515	BAR SPLICERS	EACH	26	26	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	119	119	
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18	18	
52100520	ANCHOR BOLTS, 1"	EACH	36	36	
60621900	CONCRETE MEDIAN, TYPE SM (SPECIAL)	SQ FT	662	662	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100100	TRAFFIC CONTROL AND PROTECTION, STANDARD 701316	EACH	1	1	
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1	
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3623	3623	
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63	63	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2057	2057	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	430	430	

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		018-0025 SFTY-2A	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1208	1208	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	63	63	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	2057	2057	
* 78001130	PAINT PAVEMENT MARKING - LINE 6"	FOOT	430	430	
* 78100300	REPLACEMENT REFLECTOR	EACH	6	6	
78200300	PRISMATIC CURB REFLECTOR	EACH	10	10	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	725	725	
X0321468	PLUG EXISTING DECK DRAINS	EACH	7	7	
X0322050	RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL	EACH	6	6	
X4403300	CONCRETE MEDIAN REMOVAL	SQ FT	72	72	
X7240600	REMOVE AND RE-ERECT EXISTING SIGN	EACH	2	2	
XZ191208	BRIDGE DECK MICROSILICA CONCRETE OVERLAY 3 1/4"	SQ YD	960	960	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	960	960	
Z0012750	CONCRETE MEDIAN REPAIR	SQ FT	47	47	
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	3	3	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	134	134	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	47	47	
*SPECIALTY ITEMS					