





TYPICAL PLACEMENT OF PRISMATIC CURB REFLECTORS



1. PRISMATIC REFLECTORS SHALL BE MONO-DIRECTIONAL AND POSITIONED SO THAT THE REFLECTIVE FACE IS FACING THE APPROACHING TRAFFIC.
2. PRISMATIC REFLECTORS SHALL BE SECURED IN PLACE WITH AN EPOXY ADHESIVE.
3. PRISMATIC REFLECTORS SHALL BE EITHER AMBER OR CRYSTAL IN COLOR.
4. REFER TO SCHEDULES FOR PRISMATIC REFLECTOR QUANTITIES.
5. USE A MINIMUM OF 3 REFLECTORS ON ISLAND NOSES.



SECTION VIEW

NOT TO SCALE

DISTRICT 7 DETAIL NO. 78200300

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PRISMATIC CURB REFLECTOR			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca\pwork\pwork\swartzw\dms53580\d77	346-shd-details.dgn	DRAWN -	REVISED -					116	(18-47HB-1)BR	CUMBERLAND	28	28
	PLOT SCALE = 20.000000' / IN.	CHECKED -	REVISED -					CONTRACT NO. 74346				
	PLOT DATE = 3/19/2010	DATE -	REVISED -					FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			
				SCALE: NA		SHEET NO. 1 OF 1 SHEETS		STA. TO STA.				