

EARTHWORK SCHEDULE						
LOCATION (STATION TO STATION)		EARTH EXCAVATION	ADJUSTED VOLUME	EMBANKMENT	FURNISHED EXCAVATION	
					CU YD	CU YD
US 51						
Stage I						
1145+04.76 TO 1164+48.32	US 51 - NB	163	122	120		2
1145+04.76 TO 1164+48.32	US 51 - SB	207	155	97		58
SUB - TOTAL:		370	277	217		60
Stage II						
1145+04.76 TO 1164+48.32	US 51 - NB	34	26	0		26
1145+04.76 TO 1164+48.32	US 51 - SB	30	23	0		23
SUB - TOTAL:		64	49	0		49
Stage III						
1145+04.76 TO 1164+48.32	US 51 - NB	172	129	180		-51
1145+04.76 TO 1164+48.32	US 51 - SB	152	114	222		-108
SUB - TOTAL:		324	243	402		-159
<b>TOTALS:</b>		<b>758</b>	<b>569</b>	<b>619</b>		<b>-50</b>

SEEDING SCHEDULE				
LOCATION (STATION TO STATION)		SEEDING, CLASS 2 (SPECIAL)	TEMP. EROSION CONTROL SEEDING (2 APPL.)	
			ACRE	POUND
US 51 - NB				
1145+04.74 TO 1151+57.32		0.3		69
1151+26.38 TO 1153+91.28		0.1		23
1155+64.65 TO 1158+40.01		0.2		46
1159+64.98 TO 1163+74.89		0.1		23
SUB-TOTAL:		0.7		161
PAY-TOTAL:		0.7		170
US 51 - SB				
1145+52.00 TO 1149+97.26		0.1		23
1150+42.91 TO 1153+86.12		0.3		69
1155+64.65 TO 1158+32.71		0.1		23
1158+01.15 TO 1164+48.31		0.3		69
SUB-TOTAL:		0.8		184
PAY-TOTAL:		0.8		190
I-72				
150+66.26 TO 154+12.59		0.3		69
SUB-TOTAL:		0.3		69
PAY-TOTAL:		0.3		70
<b>TOTAL:</b>		<b>1.8</b>		<b>430</b>

PERIMETER EROSION BARRIER SCHEDULE							
LOCATION (STATION TO STATION)				PERIMETER EROSION BARRIER			
				FOOT			
US 51 - NB							
1145+04.75	58.61	RT	TO	1150+40.09	115.56	RT	560.0
1151+26.38	110.42	RT	TO	1153+91.28	63.58	RT	296.0
1155+64.65	63.58	RT	TO	1158+40.01	77.04	RT	300.0
1160+38.35	88.77	RT	TO	1163+74.74	58.30	RT	351.0
SUB-TOTAL:				1,507			
US 51 - SB							
1145+51.98	59.62	LT	TO	1149+05.66	96.55	LT	372.0
1150+42.91	88.06	LT	TO	1153+86.12	63.57	LT	400.0
1155+64.65	63.58	LT	TO	1158+32.71	110.49	LT	296.0
1159+13.32	112.54	LT	TO	1164+50.78	58.04	LT	560.0
SUB-TOTAL:				1,628			
<b>TOTAL:</b>				<b>3,135</b>			

EROSION CONTROL BLANKET SCHEDULE		
LOCATION (STATION, OFFSET)		EROSION CONTROL BLANKET
		SQ YD
US 51 - NB		
1153+37.97	RT	35
1156+21.47	RT	70
SUB-TOTAL:		105
US 51 - SB		
1153+34.09	LT	92
1156+17.59	LT	35
SUB-TOTAL:		127
<b>TOTAL:</b>		<b>232</b>

INLET AND PIPE PROTECTION SCHEDULE		
LOCATION (STATION, OFFSET)		INLET AND PIPE PROTECTION
		EACH
US 51 - NB		
150+87.65	0.62' RT	1
<b>TOTAL:</b>		<b>1</b>

SURVEY MARKERS SCHEDULE		
LOCATION (STATION, OFFSET)	PERMANENT SURVEY MARKERS, TYPE I	
		EACH
US 51 OVER I-72		
TO BE DETERMINED BY ENGINEER		1
<b>TOTAL:</b>		<b>1</b>

TREE REMOVAL SCHEDULE		
LOCATION (STATION, OFFSET)		TREE REMOVAL (6 TO 15 UNITS DIAMETER)
		UNIT
US 51 - SB		
1153+27.03	77.52' LT	10
1153+50.02	74.25' LT	10
<b>TOTAL:</b>		<b>20</b>

C R PAVEMENT REMOVAL		
LOCATION		CONTINUOUSLY REINFORCED CONCRETE PAVEMENT REMOVAL
STATION	TO STATION	SQ YD
US 51 - NB		
1151+48.42	TO 1153+08.00	426
1156+47.17	TO 1158+06.20	424
Sub-Total:		850
US 51 - SB		
1151+48.42	TO 1153+07.40	424
1156+46.56	TO 1158+06.21	426
Sub-Total:		850
<b>TOTAL:</b>		<b>1700</b>

COMBINATION C&G AND MEDIAN REMOVAL					
LOCATION		COMBINATION CURB AND GUTTER REMOVAL		MEDIAN SURFACE REMOVAL	
STATION	TO STATION	FOOT	SQ FT		
US 51 - NB					
1150+57.78	RT TO 1151+48.42	RT	91		
1151+48.42	RT TO 1153+47.69	RT	199		
1156+06.77	RT TO 1158+06.20	RT	199		
1158+06.20	RT TO 1158+97.78	RT	92		
Sub-Total:			581		
US 51 - SB					
1149+72.64	LT TO 1151+48.42	LT	176		
1151+48.42	LT TO 1153+47.69	LT	199		
1156+06.77	LT TO 1158+06.20	LT	199		
1158+06.20	LT TO 1158+97.78	LT	92		
Sub-Total:			666	0	
US 51 - Median					
1149+72.64	TO 1151+48.42			2257	
1151+48.42	TO 1153+47.69			2559	
1156+06.77	TO 1158+06.20			2561	
1158+06.20	TO 1158+97.78			1176	
Sub-Total:			0	8553	
<b>TOTAL:</b>			<b>1247</b>	<b>8553</b>	

PAVED SHOULDER REMOVAL			
LOCATION		PAVED SHOULDER REMOVAL	
STATION	TO STATION	SQ YD	
US 51 - NB			
1145+04.76	TO 1151+81.82	752	
1151+81.82	TO 1152+65.71	103	
1152+15.39	TO 1153+09.34	63	
1156+48.35	TO 1158+52.64	136	
1159+12.53	TO 1159+49.58	49	
1159+49.58	TO 1163+74.87	473	
452+19.66	TO 453+06.27	38	
561+29.77	TO 562+75.82	68	
Sub-Total:		1682	
US 51 - SB			
1145+51.86	TO 1150+13.55	513	
1150+13.55	TO 1150+36.40	25	
1150+87.74	TO 1153+06.20	146	
1156+45.02	TO 1157+38.51	62	
1156+89.69	TO 1157+69.16	97	
1157+69.16	TO 1164+48.36	755	
361+29.18	TO 362+78.66	66	
252+10.76	TO 253+18.05	49	
Sub-Total:		1713	
<b>TOTAL:</b>		<b>3395</b>	

APPROACH SLAB REMOVAL			
LOCATION		APPROACH SLAB REMOVAL	
STATION	TO STATION	SQ YD	
US 51 - NB			
1153+08.35	TO 1153+49.51	220	
1156+07.17	TO 1156+47.53	193	
Sub-Total:		413	
US 51 - SB			
1153+07.03	TO 1153+47.40	193	
1156+05.05	TO 1156+46.19	215	
Sub-Total:		408	
<b>TOTAL:</b>		<b>821</b>	