

PAVEMENT MARKING SCHEDULE													
LOCATION				TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 6"	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	PAVEMENT MARKING GROOVING			
STATION	TO	STATION		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT			
US 51 - NB													
1144+71.50	RT TO	1164+07.05	RT	Main	Solid Yellow	Median RT	1936		1936	1936			
1144+93.76	RT TO	1163+85.56	RT	Main	Skip Dash (10'-30')	Lane Line RT		473	473	473			
1145+04.76	RT TO	1151+69.25	RT	Main	Solid White	EOP RT	664		664	664			
1151+69.25	RT TO	1153+61.31	RT	Main	Solid White	Gore RT - ML		192		192			
1152+67.03	RT TO	1157+26.70	RT	Main	Solid White	EOP RT	460		460	460			
1152+67.03	RT TO	1153+61.31	RT	Main	Solid White	Gore RT - RAMP		94	94	94			
1153+61.31	RT TO	1158+01.39	RT	Main	Dotted (3'-9')	Weave Ln RT		110	110	110			
1158+01.39	RT TO	1159+55.23	RT	Main	Solid White	Gore RT		154	154	154			
1159+55.23	RT TO	1163+74.70	RT	Main	Solid White	EOP RT	419		419	420			
450+00.00	RT TO	454+26.73	RT	Ramp F	Solid White	EOP Inside	427		427	427			
450+73.44	LT TO	452+27.21	LT	Ramp F	Solid White	Gore LT		154	154	154			
452+27.21	RT TO	454+26.73	RT	Ramp F	Solid Yellow	EOP Outside	200		200	200			
558+04.46	RT TO	563+56.45	RT	Ramp H	Solid White	EOP Inside	552		552	552			
558+04.46	LT TO	562+61.68	LT	Ramp H	Solid Yellow	EOP Outside	457		457	457			
562+61.68	LT TO	563+56.45	LT	Ramp H	Solid White	Gore LT		95	95	95			
Sub-Total:							5115	473	799	5115	473	799	6388
US 51 - SB													
1145+18.73	LT TO	1164+83.25	LT	Main	Solid Yellow	Median LT	1965		1965	1965			
1145+40.98	LT TO	1164+59.84	LT	Main	Skip Dash (10'-30')	Lane Line LT		480	480	480			
1145+51.86	LT TO	1149+96.82	LT	Main	Solid White	EOP LT	445		445	445			
1149+96.82	LT TO	1151+38.38	LT	Main	Solid White	Gore LT		142	142	142			
1151+38.38	LT TO	1156+16.48	LT	Main	Dotted (3'-9')	Weave Ln LT		120	120	120			
1152+27.84	LT TO	1156+87.23	LT	Main	Solid White	EOP LT	459		459	459			
1156+16.48	LT TO	1158+04.73	LT	Main	Solid White	Gore LT		188	188	188			
1156+16.48	LT TO	1156+87.23	LT	Main	Solid White	Gore LT		71	71	71			
1158+04.73	LT TO	1164+48.36	LT	Main	Solid White	EOP LT	644		644	644			
250+00.00	RT TO	254+40.79	RT	Ramp B	Solid White	EOP Inside	441		441	441			
250+87.80	LT TO	252+29.57	LT	Ramp B	Solid White	Gore LT		142	142	142			
252+29.57	LT TO	254+40.79	LT	Ramp B	Solid Yellow	EOP Outside	211		211	211			
358+03.85	RT TO	363+56.49	RT	Ramp D	Solid White	EOP Inside	553		553	553			
358+03.85	LT TO	362+42.01	LT	Ramp D	Solid Yellow	EOP Outside	438		438	438			
362+42.01	LT TO	363+56.49	LT	Ramp D	Solid White	Gore LT		114	114	114			
Sub-Total:							5156	480	777	5156	480	777	6413
TOTAL:							10271	953	1576	10271	953	1576	12801

DELINEATORS SCHEDULE						
LOCATION				DELINEATORS	DELINEATOR REMOVAL	
STATION	TO	STATION		EACH	EACH	
US 51 - NB						
558+04.46	RT TO	563+56.45	RT	Ramp H Inside	6	
558+04.46	LT TO	563+56.45	LT	Ramp H Outside	6	
450+00.00	RT TO	454+26.73	RT	Ramp F Inside	4	
450+00.00	LT TO	454+26.73	LT	Ramp F Outside	4	
Sub-Total:				20	20	
US 51 - SB						
250+00.00	RT TO	254+40.79	RT	Ramp B Inside	4	
250+00.00	LT TO	254+40.79	LT	Ramp B Outside	4	
358+03.85	RT TO	363+56.49	RT	Ramp D Inside	6	
358+03.85	LT TO	363+56.49	LT	Ramp D Outside	6	
Sub-Total:				20	20	
TOTAL:				40	40	

SIGN PANEL SCHEDULE		
LOCATION		SIGN PANEL - TYPE 1
STATION	TO	SQ FT
US 51 - NB		
1155+45.00	RT	WB I-72
Sub-Total:		135
US 51 - SB		
1154+10.00	RT	EB I-72
Sub-Total:		163
TOTAL:		298

TEMPORARY CONCRETE BARRIER SCHEDULE						
LOCATION				TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	
STATION	TO	STATION		FOOT	FOOT	
US 51 - NB						
1152+71.49	RT TO	1156+85.47	RT	Stage I	MAINLINE	
1149+64.08	RT TO	1158+06.20	RT	Stage II	MAINLINE	
1152+78.05	RT TO	1153+40.53	RT	Stage III	MAINLINE	
1155+72.78	RT TO	1156+60.11	RT	Stage III	MAINLINE	
Sub-Total:				414	414	
US 51 - SB						
1152+70.09	LT TO	1156+84.13	LT	Stage I	MAINLINE	
1151+20.54	LT TO	1159+90.60	LT	Stage II	MAINLINE	
1152+59.08	LT TO	1153+83.91	LT	Stage III	MAINLINE	
1156+20.76	LT TO	1156+58.26	LT	Stage III	MAINLINE	
Sub-Total:				414	414	
I-72						
147+86.23	RT TO	153+53.70	RT	Stage I	MAINLINE	
148+25.17	RT TO	153+50.16	RT	Stage I	RAMP B	
152+35.61	LT TO	158+02.64	LT	Stage I	MAINLINE	
152+32.44	LT TO	157+60.98	LT	Stage I	RAMP F	
Sub-Total:				567	567	
TOTAL:				3980	1140	

GUARDRAIL SCHEDULE							
LOCATION (STATION TO STATION)				GUARDRAIL REMOVAL	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	TRAFFIC BARRIER TERMINAL, TYPE 6	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL TANGENT)
STATION	TO	STATION		FOOT	FOOT	EACH	EACH
US 51 - NB							
1152+24.07	RT TO	1153+49.73	RT	126			1
1152+08.22	69.75 RT TO	1152+57.68	62.43 RT		37.5		
1152+57.68	62.43 RT TO	1152+94.97	58.67 RT			1	
1152+94.97	58.67 RT TO	1153+37.97	58.67 RT				1
Sub-Total:				126	37.5	1	1
US 51 - SB							
1156+05.45	0 LT TO	1157+31.41	0 LT	126			
1156+17.59	58.67 LT TO	1156+60.58	58.74 LT			1	
1156+60.58	58.74 LT TO	1156+97.87	62.58 LT		37.5		
1156+97.87	62.58 LT TO	1157+47.32	69.98 LT				1
Sub-Total:				126	37.5	1	1
I-72							
151+22.99	+0.00 RT TO	1153+61.46	RT	239			
Sub-Total:				239	0	0	0
TOTAL:				491	75	2	2

TREE PLANTING SCHEDULE	
LOCATION (STATION, OFFSET)	TREE, MALUS PRAIRIFIRE (PRAIRIFIRE CRABAPPLE), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED
US 51 OVER I-72	
TO BE DETERMINED BY ENGINEER	
TOTAL: 2	

TEMPORARY GUARDRAIL SCHEDULE							
LOCATION (STATION TO STATION)			TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 2	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 5	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 6
STATION	TO	STATION	FOOT	EACH	EACH	EACH	EACH
US 51 - NB							
1152+08.22	RT TO	1153+37.97	RT	37.5	1		1
1156+21.47	RT TO	1156+75.34	RT	37.5		1	
Sub-Total:				75	1	1	1
US 51 - SB							
1152+92.72	LT TO	1153+34.09	LT	37.5		1	
1156+17.59	LT TO	1157+47.32	LT	37.5			1
Sub-Total:				75		1	1
TOTAL:				150	2	2	2

BARRIER WALL AND GUARDRAIL MARKER SCHEDULE									
LOCATION				GUARDRAIL MARKERS, TYPE A	BARRIER WALL MARKERS, TYPE B	BARRIER WALL MARKERS, TYPE C	TERMINAL MARKER - DIRECT APPLIED		
STATION	TO	STATION		EACH	EACH	EACH	EACH		
US 51 - NB									
1152+08.22	69.75 RT TO	1153+37.97	58.67 RT	3					
1153+37.97	58.67 RT TO	1156+21.47	58.67 RT		5				
1152+08.22	69.75 RT TO	1156+21.47	58.67 RT				1		
1156+21.47	59.83 RT TO	1156+75.34	59.83 RT						
Sub-Total:				5	5	5	1		
US 51 - SB									
1156+17.59	58.67 LT TO	1157+47.32	69.98 LT	3					
1153+34.09	58.67 LT TO	1156+17.59	58.67 LT		5				
1157+47.32	69.98 LT TO	1153+34.09	59.83 LT				1		
1152+92.72	59.83 LT TO	1153+34.09	59.83 LT						
Sub-Total:				5	5	5	1		
TOTAL:				10	10	10	2		