

TEMPORARY PAVEMENT MARKING AND REMOVAL SCHEDULE

| LOCATION | | | | SHORT-TERM PAVEMENT MARKING | WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH | WORK ZONE PAVEMENT MARKING REMOVAL | |
|------------|-------|------------|-------|--|---|------------------------------------|-------|
| STATION | TO | STATION | STAGE | DESCRIPTION | FOOT | FOOT | SQ FT |
| US 51 - NB | | | | | | | |
| 1144+93.76 | RT TO | 1163+85.56 | RT | Main Skip Dash Lane Ln RT | 47 | | 16 |
| 1145+04.76 | RT TO | 1153+61.31 | RT | Main Diagonal White EOP RT | 34 | | 11 |
| 1153+61.31 | RT TO | 1153+22.16 | RT | Main Diagonal White EOP RT | 2 | | 1 |
| 1152+69.85 | RT TO | 1153+61.31 | RT | Main Diagonal White Gore LT | 4 | | 1 |
| 1153+22.16 | RT TO | 1156+36.12 | RT | Main Diagonal White EOP RT | 13 | | 4 |
| 1153+61.31 | RT TO | 1158+01.39 | RT | Main Skip Dash Weaving Ln | 11 | | 4 |
| 1156+36.12 | RT TO | 1157+26.70 | RT | Main Diagonal White EOP RT | 4 | | 1 |
| 1158+01.39 | RT TO | 1163+74.90 | RT | Main Diagonal White EOP RT | 23 | | 8 |
| 450+00.00 | RT TO | 454+26.73 | RT | Ramp F Diagonal White EOP Inside | 17 | | 6 |
| 450+73.44 | LT TO | 452+27.21 | RT | Ramp F Diagonal White Gore LT | 6 | | 2 |
| 452+27.21 | RT TO | 454+26.73 | RT | Ramp F Diagonal Yellow EOP Outside | 8 | | 3 |
| 558+04.46 | RT TO | 563+56.45 | RT | Ramp H Diagonal White EOP Inside | 22 | | 7 |
| 558+04.46 | LT TO | 562+61.68 | LT | Ramp H Diagonal Yellow EOP Outside | 18 | | 6 |
| 562+61.68 | RT TO | 563+56.45 | RT | Ramp H Diagonal White Gore LT | 4 | | 1 |
| 1144+71.50 | RT TO | 1164+07.05 | RT | Main Solid Yellow Median RT | | | 646 |
| 1144+93.76 | RT TO | 1163+85.56 | RT | Main Skip Dash (10'-30') Lane Ln RT | | | 237 |
| 1145+04.76 | RT TO | 1151+69.25 | RT | Main Solid White EOP RT | | | 221 |
| 1151+69.25 | RT TO | 1153+61.31 | RT | Main Solid White Gore RT | | | 128 |
| 1152+67.03 | RT TO | 1157+26.70 | RT | Main Solid White EOP RT | | | 153 |
| 1152+67.03 | RT TO | 1153+61.31 | RT | Main Solid White Gore RT | | | 63 |
| 1153+61.31 | RT TO | 1158+01.39 | RT | Main Dotted (3'-9') Weave Ln RT | | | 73 |
| 1158+01.39 | RT TO | 1159+55.23 | RT | Main Solid White Gore RT | | | 103 |
| 1159+55.23 | RT TO | 1163+74.70 | RT | Main Solid White EOP RT | | | 140 |
| 450+00.00 | RT TO | 454+26.73 | RT | Ramp F Solid White EOP Inside | | | 142 |
| 450+73.44 | LT TO | 452+27.21 | LT | Ramp F Solid White Gore LT | | | 103 |
| 452+27.21 | RT TO | 454+26.73 | RT | Ramp F Solid Yellow EOP Outside | | | 67 |
| 558+04.46 | RT TO | 563+56.45 | RT | Ramp H Solid White EOP Inside | | | 184 |
| 558+04.46 | LT TO | 562+61.68 | LT | Ramp H Solid Yellow EOP Outside | | | 152 |
| 562+61.68 | LT TO | 563+56.45 | LT | Ramp H Solid White Gore LT | | | 63 |
| 1149+83.42 | RT TO | 1151+56.97 | RT | STAGE I Main Solid White EOP RT | | 174 | |
| 1150+05.68 | RT TO | 1158+73.94 | RT | STAGE I Main Solid White Lane Line | | 868 | |
| 1150+27.93 | RT TO | 1158+51.69 | RT | STAGE I Main Solid Yellow Median RT | | 824 | |
| 1151+56.97 | RT TO | 1152+56.97 | RT | STAGE I Main Dotted White (3'-9') EOP RT | | 25 | |
| 1152+56.97 | RT TO | 1157+00.47 | RT | STAGE I Main Solid White EOP RT | | 444 | |
| 1157+00.47 | RT TO | 1158+00.47 | RT | STAGE I Main Dotted White (3'-9') EOP RT | | 25 | |
| 1158+00.47 | RT TO | 1158+96.20 | RT | STAGE I Main Solid White EOP RT | | 96 | |
| 558+47.41 | RT TO | 563+47.45 | RT | STAGE I Ramp H Solid White EOP RT | | 500 | |
| 558+47.41 | LT TO | 562+00.06 | LT | STAGE I Ramp H Solid Yellow EOP LT | | 353 | |
| 562+00.06 | LT TO | 562+57.68 | LT | STAGE I Ramp H Solid White EOP LT | | 58 | |
| 1157+00.47 | RT TO | 1157+26.70 | RT | STAGE I Ramp F Solid White EOP RT | | 26 | |
| 450+00.00 | RT TO | 452+73.49 | RT | STAGE I Ramp F Solid White EOP RT | | 273 | |
| 450+72.19 | LT TO | 451+21.92 | LT | STAGE I Ramp F Solid White EOP LT | | 50 | |
| 451+21.92 | LT TO | 452+73.49 | LT | STAGE I Ramp F Solid Yellow EOP LT | | 152 | |
| 1145+04.76 | RT TO | 1151+15.39 | RT | STAGE II Main Solid White EOP RT | | 611 | |
| 1144+93.76 | RT TO | 1163+85.56 | RT | STAGE II Main Solid White Lane Line | | 1892 | |
| 1144+71.50 | RT TO | 1164+07.05 | RT | STAGE II Main Solid Yellow Median RT | | 1936 | |
| 1151+15.39 | RT TO | 1152+15.39 | RT | STAGE II Main Dotted White (3'-9') EOP RT | | 25 | |
| 1152+15.39 | RT TO | 1158+52.71 | RT | STAGE II Main Solid White EOP RT | | 637 | |
| 1158+52.71 | RT TO | 1159+52.61 | RT | STAGE II Main Dotted White (3'-9') EOP RT | | 25 | |
| 1159+52.61 | RT TO | 1163+74.90 | RT | STAGE II Main Solid White EOP RT | | 422 | |
| 558+04.46 | RT TO | 563+04.46 | RT | STAGE II Ramp H Solid White EOP RT | | 500 | |
| 558+04.46 | LT TO | 561+51.17 | LT | STAGE II Ramp H Solid Yellow EOP LT | | 347 | |
| 561+51.17 | LT TO | 562+13.04 | LT | STAGE II Ramp H Solid White EOP LT | | 62 | |
| 451+26.73 | RT TO | 454+26.73 | RT | STAGE II Ramp F Solid White EOP RT | | 300 | |
| 452+21.24 | LT TO | 452+75.42 | LT | STAGE II Ramp F Solid White EOP LT | | 54 | |
| 452+75.42 | LT TO | 454+26.73 | LT | STAGE II Ramp F Solid Yellow EOP LT | | 151 | |
| 1145+04.76 | RT TO | 1163+74.90 | RT | STAGE III Main Solid White EOP RT | | 1870 | |
| 1144+93.76 | RT TO | 1163+85.56 | RT | STAGE III Main Solid White Lane Line | | 1892 | |
| 1144+71.50 | RT TO | 1164+07.05 | RT | STAGE III Main Solid Yellow Median RT | | 1936 | |
| 1153+61.31 | RT TO | 1158+01.39 | RT | STAGE III Main Dotted White (3'-9') Lane Ln RT | | 440 | |
| 1152+67.03 | RT TO | 1153+61.31 | RT | STAGE III Main Solid White Gore RT | | 94 | |
| 1152+67.03 | RT TO | 1157+26.70 | RT | STAGE III Main Solid White EOP RT | | 460 | |
| 558+04.46 | RT TO | 563+56.45 | RT | STAGE III Ramp H Solid White EOP RT | | 552 | |
| 558+04.46 | LT TO | 562+61.85 | LT | STAGE III Ramp H Solid Yellow EOP LT | | 457 | |
| 562+61.85 | LT TO | 563+56.45 | LT | STAGE III Ramp H Solid White GORE LT | | 95 | |
| 450+00.00 | RT TO | 454+26.73 | RT | STAGE III Ramp F Solid White EOP RT | | 427 | |
| 450+73.44 | LT TO | 452+27.21 | LT | STAGE III Ramp F Solid White GORE LT | | 154 | |
| 452+27.21 | LT TO | 454+26.73 | LT | STAGE III Ramp F Solid Yellow EOP LT | | 200 | |
| Sub-Total: | | | | | 213 | 19407 | 2546 |

TEMPORARY PAVEMENT MARKING AND REMOVAL SCHEDULE (CONT.)

| LOCATION | | | | SHORT-TERM PAVEMENT MARKING | WET TEMPORARY PAVEMENT MARKING TAPE, TYPE III, 4 INCH | WORK ZONE PAVEMENT MARKING REMOVAL | |
|---------------|-------|------------|-------|--|---|------------------------------------|-------|
| STATION | TO | STATION | STAGE | DESCRIPTION | FOOT | FOOT | SQ FT |
| US 51 - SB | | | | | | | |
| 1145+40.98 | LT TO | 1164+59.84 | LT | Main Skip Dash Lane Ln LT | 48 | | 16 |
| 1145+51.97 | LT TO | 1151+38.38 | LT | Main Diagonal White EOP LT | 23 | | 8 |
| 1151+38.38 | LT TO | 1156+16.48 | LT | Main Skip Dash Weaving Ln | 12 | | 4 |
| 1152+27.84 | LT TO | 1153+19.44 | LT | Main Diagonal White EOP LT | 4 | | 1 |
| 1153+19.44 | LT TO | 1156+32.94 | LT | Main Diagonal White EOP LT | 13 | | 4 |
| 1156+16.48 | LT TO | 1164+48.32 | LT | Main Diagonal White EOP LT | 33 | | 11 |
| 1156+16.48 | LT TO | 1156+87.48 | LT | Main Diagonal White Gore LT | 3 | | 1 |
| 1156+32.94 | LT TO | 1156+87.23 | LT | Main Diagonal White Gore LT | 2 | | 1 |
| 250+00.00 | RT TO | 254+40.79 | RT | Ramp B Diagonal White EOP Inside | 18 | | 6 |
| 250+87.80 | LT TO | 252+29.57 | LT | Ramp B Diagonal White Gore LT | 6 | | 2 |
| 252+29.57 | LT TO | 254+40.79 | LT | Ramp B Diagonal Yellow EOP Outside | 8 | | 3 |
| 358+03.85 | RT TO | 363+56.49 | RT | Ramp D Diagonal White EOP Inside | 22 | | 7 |
| 358+03.85 | LT TO | 362+42.01 | LT | Ramp D Diagonal Yellow EOP Outside | 18 | | 6 |
| 362+42.01 | LT TO | 363+56.49 | LT | Ramp D Diagonal White Gore LT | 5 | | 2 |
| 1145+18.73 | LT TO | 1164+83.25 | LT | Main Solid Yellow Median LT | | | 656 |
| 1145+40.98 | LT TO | 1164+59.84 | LT | Main Skip Dash (10'-30') Lane Ln LT | | | 240 |
| 1145+51.86 | LT TO | 1149+96.82 | LT | Main Solid White EOP LT | | | 148 |
| 1149+96.82 | LT TO | 1151+38.38 | LT | Main Solid White Gore LT | | | 95 |
| 1151+38.38 | LT TO | 1156+16.48 | LT | Main Dotted (3'-9') Weave Ln LT | | | 80 |
| 1152+27.84 | LT TO | 1156+87.23 | LT | Main Solid White EOP LT | | | 153 |
| 1156+16.48 | LT TO | 1158+04.73 | LT | Main Solid White Gore LT | | | 125 |
| 1156+16.48 | LT TO | 1156+87.23 | LT | Main Solid White Gore LT | | | 47 |
| 1158+04.73 | LT TO | 1164+48.36 | LT | Main Solid White EOP LT | | | 215 |
| 250+00.00 | RT TO | 254+40.79 | RT | Ramp B Solid White EOP Inside | | | 147 |
| 250+87.80 | LT TO | 252+29.57 | LT | Ramp B Solid White Gore LT | | | 95 |
| 252+29.57 | LT TO | 254+40.79 | LT | Ramp B Solid Yellow EOP Outside | | | 70 |
| 358+03.85 | RT TO | 363+56.49 | RT | Ramp D Solid White EOP Inside | | | 184 |
| 358+03.85 | LT TO | 362+42.01 | LT | Ramp D Solid Yellow EOP Outside | | | 146 |
| 362+42.01 | LT TO | 363+56.49 | LT | Ramp D Solid White Gore LT | | | 76 |
| 1150+30.54 | LT TO | 1151+55.09 | LT | STAGE I Main Solid White EOP LT | | 125 | |
| 1150+52.80 | LT TO | 1159+48.94 | LT | STAGE I Main Solid White Lane Line | | 896 | |
| 1150+75.05 | LT TO | 1159+26.69 | LT | STAGE I Main Solid Yellow Median LT | | 852 | |
| 1151+55.09 | LT TO | 1152+55.09 | LT | STAGE I Main Dotted White (3'-9') EOP LT | | 25 | |
| 1152+55.09 | LT TO | 1156+98.59 | LT | STAGE I Main Solid White EOP LT | | 444 | |
| 1156+98.59 | LT TO | 1157+98.59 | LT | STAGE I Main Dotted White (3'-9') EOP LT | | 25 | |
| 1157+98.59 | LT TO | 1159+71.20 | LT | STAGE I Main Solid White EOP LT | | 173 | |
| 250+00.00 | RT TO | 252+72.53 | RT | STAGE I Ramp B Solid White EOP RT | | 273 | |
| 1152+27.84 | LT TO | 1152+55.09 | LT | STAGE I Ramp B Solid White EOP LT | | 27 | |
| 250+71.21 | LT TO | 251+20.81 | LT | STAGE I Ramp B Solid White EOP LT | | 50 | |
| 251+20.81 | LT TO | 252+72.53 | LT | STAGE I Ramp B Solid Yellow EOP LT | | 152 | |
| 358+46.15 | RT TO | 363+46.25 | RT | STAGE I Ramp D Solid White EOP RT | | 500 | |
| 358+46.15 | LT TO | 361+99.13 | LT | STAGE I Ramp D Solid Yellow EOP LT | | 353 | |
| 361+99.13 | LT TO | 362+56.55 | LT | STAGE I Ramp D Solid White EOP LT | | 57 | |
| 1145+51.97 | LT TO | 1149+87.83 | LT | STAGE II Main Solid White EOP LT | | 436 | |
| 1145+40.98 | LT TO | 1164+59.84 | LT | STAGE II Main Solid White Lane Line | | 1919 | |
| 1145+18.73 | LT TO | 1164+83.25 | LT | STAGE II Main Solid Yellow Median LT | | 1965 | |
| 1149+87.83 | LT TO | 1150+87.74 | LT | STAGE II Main Dotted White (3'-9') EOP LT | | 25 | |
| 1150+87.74 | LT TO | 1157+39.53 | LT | STAGE II Main Solid White EOP LT | | 652 | |
| 1157+39.53 | LT TO | 1158+39.53 | LT | STAGE II Main Dotted White (3'-9') EOP LT | | 25 | |
| 1158+39.53 | LT TO | 1164+48.32 | LT | STAGE II Main Solid White EOP LT | | 609 | |
| 251+41.00 | RT TO | 254+40.79 | RT | STAGE II Ramp B Solid White EOP RT | | 300 | |
| 252+34.48 | LT TO | 252+90.07 | LT | STAGE II Ramp B Solid White EOP LT | | 56 | |
| 252+90.07 | LT TO | 254+40.79 | LT | STAGE II Ramp B Solid Yellow EOP LT | | 151 | |
| 358+03.85 | RT TO | 363+03.85 | RT | STAGE II Ramp D Solid White EOP RT | | 500 | |
| 358+03.85 | LT TO | 361+50.69 | LT | STAGE II Ramp D Solid Yellow EOP LT | | 347 | |
| 361+50.69 | LT TO | 362+42.45 | LT | STAGE II Ramp D Solid White EOP LT | | 62 | |
| 1145+51.97 | LT TO | 1164+48.36 | LT | STAGE III Main Solid White EOP LT | | 1896 | |
| 1145+40.98 | LT TO | 1164+59.84 | LT | STAGE III Main Solid White Lane Line | | 1919 | |
| 1145+18.73 | LT TO | 1164+83.25 | LT | STAGE III Main Solid Yellow Median LT | | 1965 | |
| 1151+38.38 | LT TO | 1156+16.48 | LT | STAGE III Main Dotted White (3'-9') Lane Ln LT | | 120 | |
| 1152+27.84 | LT TO | 1156+87.23 | LT | STAGE III Main Solid White EOP LT | | 459 | |
| 1156+16.48 | LT TO | 1156+87.23 | LT | STAGE III Main Solid White Gore LT | | 71 | |
| 250+00.00 | RT TO | 254+40.79 | RT | STAGE III Ramp B Solid White EOP RT | | 441 | |
| 250+87.80 | LT TO | 252+29.57 | LT | STAGE III Ramp B Solid White Gore LT | | 142 | |
| 252+29.57 | LT TO | 254+40.79 | LT | STAGE III Ramp B Solid Yellow EOP LT | | 211 | |
| 358+03.85 | RT TO | 363+56.49 | RT | STAGE III Ramp D Solid White EOP RT | | 553 | |
| 358+03.85 | LT TO | 362+42.14 | LT | STAGE III Ramp D Solid Yellow EOP LT | | 438 | |
| 362+42.14 | LT TO | 363+56.49 | LT | STAGE III Ramp D Solid White EOP LT | | 114 | |
| Sub-Total: | | | | | 215 | 19328 | 2549 |
| TOTAL: | | | | 428 | 38735 | 5095 | |