

MATCHLINE STA. 1149+50.00

STA. 1145+51.97

1145+00

STA. 1145+04.76

STA. 1145+51.97 TO STA. 1149+50.00  
PIPE UNDERDRAIN REMOVAL,  
398 L.F.  
STAGE I

STA. 1145+51.97 TO STA. 1149+50.00  
PAVED SHOULDER REMOVAL,  
442 SQ. YD.  
STAGE I

STA. 253+18.05 TO STA. 252+78.10 (RAMP "B")  
PIPE UNDERDRAIN REMOVAL,  
44 L.F.  
STAGE I  
STA. 253+18.05 TO STA. 252+78.10 (RAMP "B")  
PAVED SHOULDER REMOVAL,  
20 SQ. YD.  
STAGE I


STA. 1145+04.76 TO STA. 1149+50.00  
PIPE UNDERDRAIN REMOVAL,  
445 L.F.  
STAGE I

STA. 1145+04.76 TO STA. 1149+50.00  
PAVED SHOULDER REMOVAL,  
495 SQ. YD.  
STAGE I

STA. 1147+35.15 TO STA. 1149+50.00  
PAVEMENT REMOVAL (PCC PAVEMENT, 10"),  
(PLACED IN STAGE I) (SHADED)  
113 SQ. YD.  
STAGE III

NOTE:

1. EXISTING PAVEMENT MARKINGS TO BE REMOVED WHEN IN CONFLICT WITH STAGING AND PERMANENT PAVEMENT MARKINGS. SEE STAGING AND PAVEMENT MARKING PLAN SHEETS AND SCHEDULES FOR LOCATIONS OF PAVEMENT MARKING REMOVAL.
2. CONTRACTOR TO SAWCUT ALONG EXISTING PAVEMENT AND SHOULDER AS NECESSARY FOR REMOVAL TO CONSTRUCT PAVEMENT WIDENING. COST OF SAWCUT INCLUDED IN COST OF REMOVAL ITEM FOR WHICH THE SAWCUT IS BEING MADE.
3. REMOVAL OF OUTLET AND HEADWALL AT EXISTING PIPE UNDERDRAIN OUTLETS TO BE INCLUDED IN COST OF PIPE UNDERDRAIN REMOVAL.
4. LIMITS OF GUARDRAIL REMOVAL NEAR STRUCTURES MAY VARY IN THE FIELD.
5. REMOVAL OF RAISED REFLECTIVE PAVEMENT MARKERS WITHIN LOCATIONS OF PAVEMENT REMOVAL AREAS SHALL BE INCLUDED IN THE COST OF PAVEMENT REMOVAL. IF DIRECTED BY ENGINEER, LENSES MAY BE REMOVED PRIOR TO PAVEMENT REMOVAL FOR STAGING CONFLICTS. COST OF LENSE REMOVAL INCLUDED IN COST OF RAISED REFLECTIVE PAVEMENT MARKER, REFLECTOR REMOVAL.



FILE NAME =	USER NAME = mjoost	DESIGNED - MLS	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>REMOVAL PLAN - US 51</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
P:\080276\US 51 over I-72\4-CADD\4.2-TR	SHEETS\0774387-shr-rem-001.dgn	DRAWN - MLS	REVISED -			322	(58-64HB-1)B-1	MACON	149	13	
	PLOT SCALE = 20.0000' / in.	CHECKED - SJK	REVISED -			US ROUTE 51			CONTRACT NO. 74387		
	PLOT DATE = 3/12/2010	DATE -	REVISED -			FED. ROAD DIST. NO. 7   ILLINOIS   FED. AID PROJECT					
					SCALE: 1:20	SHEET NO. 1 OF 4 SHEETS		STA. 1144+00 TO STA. 1149+50			