

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER
	FEET	FT	SQ FT	FT	FT	EACH
80+05 TO 137+62	5757.0	2302.8	191.9	12713.3	12713.3	72
137+62 TO 146+33	871.0	348.4	29.0	2830.8	2830.8	11
146+33 TO 150+64	431.0	172.4	14.4	969.8	969.8	5
150+64 TO 153+61	297.0	118.8	9.9	965.3	965.3	4
153+61 TO 155+86	225.0	90.0	7.5	900.0	900.0	3
155+86 TO 158+95	309.0	123.6	10.3	1004.3	1004.3	4
158+95 TO 207+28	4833.0	1933.2	161.1	10794.3	10794.3	60
TOTALS	12723	5089	424	30178	30178	159

PAVING SCHEDULE

STATION TO STATION	LENGTH	PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	HMA SURFACE COURSE, MIX "C", NTO	LEVELING BINDER (MACHINE METHOD), NTO	CLASS D PATCHES, TYPE IV, 15 INCH	HMA SURFACE REMOVAL - BUTT JOINT	HMA SURFACE REMOVAL, 1/2"	HOT-MIX ASPHALT REMOVAL, 2 1/4"	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP (SPECIAL)	TEMPORARY RAMP
	FEET	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	SQ YD	TON	SQ YD	SQ YD
80+05 TO 104+08	2403.0	25.0	6675.0	667.5	13.4	560.7	280.4	0.0	97.2	6550.0	0.0	111.7	0.0	34.7
104+08 TO 105+92	184.0	25.0	511.1	51.1	1.0	42.9	21.5	0.0	0.0	0.0	511.0	6.3	32.9	0.0
105+92 TO 121+45	1553.0	25.0	4313.9	431.4	8.6	362.4	181.2	0.0	0.0	4313.9	0.0	79.3	0.0	0.0
121+45 TO 121+77	32.0	25.0	88.9	8.9	0.2	7.5	3.7	88.9	0.0	88.9	0.0	1.8	0.0	0.0
121+77 TO 207+28	8551.0	25.0	23752.8	2375.3	47.5	1995.2	997.6	0.0	97.2	23669.4	0.0	403.0	0.0	34.7
TOTALS	12723	-	35342	3534	71	2969	1484	89	194	34622	511	602	33	70