

SHOULDER SCHEDULE

STATION TO STATION			SIDE	LENGTH	EXCAVATING AND GRADING EXISTING SHOULDER	AGGREGATE SHOULDERS, TYPE B	HOT-MIX ASPHALT SHOULDERS, 8"	SHOULDER RUMBLE STRIP	
									LT/RT
0+00	TO	301+12.50	RT	30113	273	828	9104	27779	
8+65	TO	301+12.50	LT	29248	260	761	8679	27162	
301+12.50	TO	301+77.5	LT & RT	65	-	-	-	-	
301+77.5	TO	550+90	RT	24913	218	680	7453	24189	
301+77.5	TO	551+20	LT	24943	196	687	6684	24693	
TOTALS					109280	947	2956	31920	103821

PAVEMENT MARKING SCHEDULE

STATION TO STATION			LENGTH	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 6"	PAINT PAVEMENT MARKING - LINE 12"	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS
0+00	TO	14+10	1410	9972	300	0	93.6
14+10	TO	301+12.50	28703	69787	100	132	46.8
301+12.50	TO	301+77.50	65	146	0	0	0.0
301+77.50	TO	551+20	24943	62029	175	90	109.2
TOTALS			55120	141934	575	222	250