

90% FED./10% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE
CODE NO	ITEM	UNIT		SFTY-2A
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	28	28
25001000	SEEDING, CLASS 2 (SPECIAL)	ACRE	0.5	0.5
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	51	51
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	7	7
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	830	830
40600300	AGGREGATE (PRIME COAT)	TON	17	17
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	174	174
40600990	TEMPORARY RAMP	SQ YD	46	46
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	349	349
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	4	4
44000196	HOT-MIX ASPHALT SURFACE REMOVAL, SPECIAL	SQ YD	4151	4151
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	40	40
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	60	60
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SQ YD	333	333
48101200	AGGREGATE SHOULDERS, TYPE B	TON	228	228
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1868	1868
67100100	MOBILIZATION	L SUM	1	1
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	456	456
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	3431	3431
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	51	51
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	6303	6303
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	213	213

*Specialty Items