SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A	XO10-2A
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	6	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2	2	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1795	1795	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	6837	6837	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2350	2350	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	72	72	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3022	3022	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1175	1175	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1175	1175	
* 72000100	SIGN PANEL - TYPE 1	SQ FT	10	10	
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	24	24	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	32	32	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	8359	8359	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	179	179	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	24	24	
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	507	507	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	65	65	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	2		2
* 78200200	BIDIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	4	4	
* 78200305	PRISMATIC BARRIER REFLECTOR	EACH	4		4
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	14	14	
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1565	1565	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	28	28	
X0323265	REMOVE EXISTING RIPRAP	SQ YD	1026	1026	
X7200200	WIDE LOAD SIGNING	L SUM	1	1	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0064505	SECTION CORNER MARKERS	EACH	1	1	

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A	

* Specialty Items

FILE NAME = c:\pw_work\PWIDOT\GELINH\dms52514\pln002a.dgn	USER NAME = gelinh	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/22/2010	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. 2 OF 2 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
682	21BR, 21-1-1		77	4
			CONTRACT NO. 76126	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		