

TEMPORARY PAVEMENT MARKING SCHEDULE

STAGE	STATION	RT/LT	EDGE LINES	PAVEMENT MARKING			SHORT TERM PAVEMENT MARKING (FT)	WORK ZONE PAVEMENT REMOVAL (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)	RAISED REF. PAVEMENT MARKER REMOVAL (EA)
				LINE 4" PAVEMENT (FT)	LINE 6" (FT)	LINE 24" (FT)				
STAGE 1	785+15.75 TO 802+25.00	RT	EDGE LINES	3418.50				1139.5		
	785+15.75	RT	STOP BAR			12		24.0		
	787+12.50 TO 798+87.50		TEMP. BARR.		1175.0					
	802+25.00	LT	STOP BAR			12		24.0		
	100+42.00	LT	STOP BAR			12		24.0		
	784+50.00 TO 805+10.00	CL								26
STAGE 2	785+15.75 TO 805+10.00	RT/LT	EDGE LINES				1196.55	398.9	1329.5	
	785+15.75 TO 805+10.00	CL	SKIP DASH				598.28	199.4	166.2	
	100+42.00 TO 101+33.59	RT/LT	EDGE LINES						61.1	
	100+42.00 TO 101+33.59	CL	SKIP DASH						7.6	2
	785+15.75 TO 802+25.00	RT/LT	EDGE LINES	3418.50				1139.5		
	785+15.75	RT	STOP BAR			12		24.0		
	787+12.50 TO 798+87.50		TEMP. BARR.		1175.0					
	802+25.00	LT	STOP BAR			12		24.0		
100+42.00	LT				12		24.0			
SUB-TOTAL										
TOTAL				6837.0	2350.0	72.0	1794.8	3021.3	1564.4	28

TREE REMOVAL SCHEDULE

STATION	OFFSET	RT/LT	6 TO 15 UNITS				OVER 15 UNITS						
786+22.54	38.5	RT			12								
786+22.98	38.8	RT	6										
786+61.93	37.7	RT	6										
786+62.70	38.7	RT	6										
786+62.99	37.3	RT			12								
787+37.95	37.9	RT				14							
788+10.72	38.4	RT				14							
788+41.02	37.1	RT						18					
788+67.49	40.5	RT							42				
788+89.32	47.7	RT				14							
789+01.35	47.5	RT						16					
789+56.61	39.5	RT				14							
789+98.25	36.5	RT							22				
793+01.85	72.3	RT								50			
793+06.50	59.8	RT						18					
SUB-TOTAL			18	0	0	24	56	0	16	36	22	42	50
TOTAL			98				166						

RIPRAP SCHEDULE

LOCATION	RIPRAP A5 (SQ YD)	FILTER FABRIC (SQ YD)
CHANNEL		
STA 0+2.50 TO STA 1+58.00 RT/LT	1936.58	1936.58
DITCH		
STA 793+31.50 TO STA 797+00.00 RT	1342.16	1342.16
STA 802+00.00 TO STA 802+50.00 RT	135.22	135.22
TOTAL	3413.96	3413.96

REMOVAL SCHEDULE

STATION	HMA SURF REMOVAL VARIABLE DEPTH (SQ YD)	BIT. CONC. SHOULDER REMOVAL (SQ YD)	PVMT REMOVAL (SQ YD)	SPBGR (FT)	RIPRAP (FT)
786+00.00 TO 788+32.00 RT/LT	567.11				
786+00.00 TO 789+84.65 RT		128.22			
786+00.00 TO 789+95.50 LT		131.83			
786+00.00 TO 788+32.00 LT			77.33		
789+84.65 TO 792+61.50 RT		285.81			
789+95.50 TO 792+61.50 LT		207.24			
790+35.00 TO 792+61.50 RT				226.50	
791+09.50 TO 792+61.50 LT				152.00	
791+89.63 TO 792+61.50 RT/LT			175.68		
791+89.63 TO 792+61.50 LT			23.96		
793+14.15 TO 793+57.63 RT/LT			106.28		
793+14.15 TO 793+57.63 LT			14.49		
793+14.00 TO 795+41.50 LT				227.50	
793+14.15 TO 795+76.13 LT		268.00			
793+14.00 TO 796+29.50 RT				315.50	
793+14.15 TO 796+43.20 RT		379.61			
793+51.40 TO 797+00.00 RT					932.14
795+76.13 TO 800+75.40 LT		166.42			
801+60.64 TO 803+01.40 LT		46.92			
796+43.20 TO 802+62.70 RT		206.50			
797+82.00 TO 805+00.00 RT/LT	1755.11				
802+03.00 TO 802+51.30 RT					93.50
TOTAL	2322.22	1820.56	397.75	921.50	1025.64

TEMPORARY EROSION CONTROL SCHEDULE

LOCATION	RT/LT	TEMP. EROS. CONTROL SEEDING (POUND)	MULCH METHOD 1 (ACRE)	PERIMETER EROSION BARRIER (FOOT)	INLET & PIPE PROTECTION (EACH)	TEMPORARY DITCH CHECK (FOOT)			
						STATION	LT	RT	
786+00.00 TO 788+00.00	RT			230.00		786+00.00	15.00		
788+00.00 TO 792+30.00	LT			430.00		787+00.00	15.00		
						788+00.00	15.00		
786+00.00 TO 805+00.00	LT	85.63	0.95			794+00.00	17.00		
786+00.00 TO 805+00.00	RT	130.82	1.45			794+00.00	17.00		
788+00.00 TO 792+30.00	RT			430.00		795+00.00	17.00		
						796+00.00	17.00		
						797+00.00	17.00		
794+00.00 TO 798+00.00	LT					798+00.00	17.00		
794+00.00 TO 802+00.00	RT					799+00.00	17.00		
795+00.00 TO 800+50.00	LT			550.00		800+00.00	17.00		
100+38.00 TO 101+33.59	RT/LT			254.00		801+00.00	13.00		
801+73.00 TO 805+00.00	LT			352.00		802+00.00	11.00		
802+86.71	SIDE ST RT				1	804+00.00	15.00		
TOTAL						216.44	2.40	2246.00	1
SUB TOTAL						79.00	156.00		
TOTAL						235.00			

SEEDING SCHEDULE

LOCATION	SEEDING CLASS 2 (ACRE)	NITROGEN FERT. NUTR (POUND)	PHOSPHORUS FERT. NUTR (POUND)	POTASSIUM FERT. NUTR (POUND)	MULCH METHOD 1 (ACRE)
785+00.00 TO 805+00.00 LT	0.95	85.63	85.63	85.63	0.95
785+00.00 TO 805+00.00 RT	1.45	130.82	130.82	130.82	1.45
TOTAL	2.40	216.45	216.45	216.45	2.40