

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
310	60-16	MADISON	662	6
STA.		TO STA.		
FED. ROAD DIST. NO. - ILLINOIS		FED. AID PROJECT		
CONTRACT NO. 76311				

ILLINOIS DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY	ROADWAY	ROADWAY	ROADWAY				
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 15% STATE 5% CITY				
				I000-2A	I000-2A	I000-2A	Y031-F				
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	7766	134	5422	2210					
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	575	575							
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	1841	16	1402	423					
40701871	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/2"	SQ YD	37738	37738							
40701966	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 14 1/4"	SQ YD	6560	6560							
40701996	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 15 3/4"	SQ YD	80011	80011							
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	13.7	13.4	0.3						
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	1276	1254	22						
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	220	220							
42001300	PROTECTIVE COAT	SQ YD	8370	5820	1220	1330					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	723	723							
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2136	1910	226						
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	706	706							
44000100	PAVEMENT REMOVAL	SQ YD	50608	48747	1712	149					
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	3351		2052	1299					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	4099	2667	1432						
44000400	GUTTER REMOVAL	FOOT	14667	12543	2124						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1350			1350					
44003100	MEDIAN REMOVAL	SQ FT	3375			3375					
44201777	CLASS D PATCHES, TYPE II, 11 INCH	SQ YD	175	84	13	78					
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	8266		8266						
48101200	AGGREGATE SHOULDERS, TYPE B	TON	15978	15255	333	390					
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	47433	46343	664	426					
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1						
54001003	BOX CULVERT END SECTION, CULVERT NO.3	EACH	2	2							
54001026	BOX CULVERT END SECTION, CULVERT NO.26	EACH	2	2							
54001034	BOX CULVERT END SECTION, CULVERT NO.34	EACH	2	2							
54010504	PRECAST CONCRETE BOX CULVERT 5' X 4'	FOOT	322	322							
54010603	PRECAST CONCRETE BOX CULVERT 6' X 3'	FOOT	42	42							
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	5	1	3	1					

PLOT DATE = #DATE#  
 FILE NAME = #FILE#  
 PLOT SCALE = #SCALE#  
 REFERENCE = #REF#

Rev.