

THERMOPLASTIC PAVEMENT MARKING SCHEDULE										RAISED REFLECTIVE PAVEMENT MARKERS			PRISMATIC CURB REFLECTOR
DESIGNATION	BEGIN STATION	END STATION	4" YELLOW	4" WHITE	8" WHITE	12" WHITE	12" YELLOW	24" WHITE	LETTERS & SYMBOLS*	ONE WAY CRYSTAL	ONE WAY AMBER	TWO WAY AMBER	ONE WAY AMBER
			(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ FT)	(EACH)	(EACH)	(EACH)	(EACH)
US 67 (Godfrey Road)	165+45.00	168+35.00	968	255			35		31.2	8	8	6	
US 67 (Godfrey Road)	168+35.00	171+00.00	544	638	46	22			62.4	19	2	6	
US 67 (Godfrey Road)	171+00.00	177+00.00	1068	675	29		8	84	62.4	22	6	7	
US 67 (Godfrey Road)	177+00.00	57+00.00	3812	2252			690		65.9	24	32	8	
			6392	3820	75	22	733	84	222	73	48	27	0
IL 111	1172+06.00	1174+00.00	240	114	360	475		42	76.3	3			3
IL 111	1174+00.00	1179+40.00	1080	1280	90				15.6	14			14
			1320	1394	450	475	0	42	92	17	0	0	17
Ramp A	00+00.00	19+17.61	1262	2020	720				6.9	40			
Ramp B	09+11.00	35+00.00	1964	1911					6.9				
Ramp B	35+00.00	47+03.00		1747	40				1.7				
FAP Route 310	91+50.00	110+00.00	3600	3850					19.1	45			
FAP Route 310	110+00.00	132+00.00	4400	4665		210			24.2	55			
FAP Route 310	132+00.00	142+00.00	2000	2500					13.9	25			
FAP Route 310	142+00.00	152+50.00	1736	3193				18	156.0	44			
FAP Route 310	152+50.00	163+50.00	1970	2531					13.9	28			
FAP Route 310	163+50.00	174+50.00	1957	2630	648	254	203		131.7	54			
FAP Route 310	174+50.00	198+00.00	4405	5950	230	30			43.3	67			
FAP Route 310	198+00.00	209+00.00	1829	3370					147.3	46			
FAP Route 310	209+00.00	225+00.00	1690	2774				20	19.1	16			
Benjamin Road	10+00.00	11+50.00	30										24
Access Road 1	10+00.00	73+22.00	1565	12,342		48							12
Access Road 2	10+00.00	41+08.00	770	6,140									22
Access Road 3	10+00.00	21+33.00	270	2,245									21
Beuttel Road	05+20.00	10+00.00											12
Lagemann Road	10+00.00	24+00.00	2560	2,500									16
Davis Lane	02+75.00	10+00.00											
			32008	60368	1638	542	203	145	584	420	0	0	0
TOTAL			39720	65582	2163	1039	936	271	898	510	48	27	17

\* UNDERDRAIN TRIANGLES WILL BE PAID FOR AS THERMOPLASTIC LETTERS & SYMBOLS (1 TRIANGLE EQUALS 1.73 SQ FT)

SHORT TERM PAVEMENT MARKING						
DESIGNATION	LOCATION		1st APPLICATION		2nd APPLICATION	
	BEGIN STA	END STA	4" YELLOW (LIN FT)	4" WHITE (LIN FT)	4" YELLOW (LIN FT)	4" WHITE (LIN FT)
US 67 (Godfrey Road)	165+45.00	56+44.00	610	454		
IL 111	1172+00	1179+40	150		1268	
SIDE ROADS AND ACCESS ROADS			1268			
FAP Route 310 SB	104+77	136+00		312		
FAP Route 310 NB	139+58	179+00		394		
FAP Route 310 SB	181+50	221+04		395		
TOTAL			2028	1555	1268	0

WORK ZONE PAVEMENT MARKING REMOVAL					
DESIGNATION	LOCATION		LENGTH (FT)	SIZE (IN)	AREA (SQ FT)
	BEGIN STA	END STA			
US 67 (Godfrey Road)	165+45.00	57+00.00	17588	4	5863
US 67 (Godfrey Road)	168+23.00	57+00.00	86	12	86
US 67 (Godfrey Road)	165+45.00	168+23.00	31.2		32
US 67 (Godfrey Road)	168+23.00	171+00.00	62.4		63
US 67 (Godfrey Road)	171+00.00	177+00.00	62.4		63
US 67 (Godfrey Road)	177+00.00	57+00.00	62.4		63
IL 111	1172+86	1179+40	5620	4	1874
IL 111	1171+50	1172+00	40	12	40
IL 111	1172+06	1174+00	72.8		73
IL 111	1174+00	1180+00	15.6		16
US 67 (Godfrey Road) - FAP 310	57+00	103+95	1965	4	655
CROSS OVER DETAIL NO. 1	136+00	142+50	3000	4	1000
CROSS OVER DETAIL NO. 1	0+00	7+11	2352	4	784
FAP Route 310 SB	111+00	136+00	5630	4	1877
CROSS OVER DETAIL NO. 2	0+00	13+06	5624	4	1875
CROSS OVER DETAIL NO. 2	0+00	5+78	2712	4	904
FAP Route 310 NB	144+25	179+00	8740	4	2914
CROSS OVER DETAIL NO. 3	0+00	11+85	5140	4	1714
CROSS OVER DETAIL NO. 4	0+00	8+04	3616	4	1206
FAP Route 310 SB	185+86	221+00	7908	4	2636
CROSS OVER DETAIL NO. 4 (ST 2)	217+50	227+50	4000	4	1334
CROSS OVER DETAIL NO. 4 (ST 3)	217+40	229+00	3860	4	1287
TOTAL					26359

POLYUREA PAVEMENT MARKING SCHEDULE								
STRUCTURE NO.	DESIGNATION	BEGIN STATION	END STATION	4" YELLOW	4" WHITE	8" WHITE	12" WHITE	LETTERS & SYMBOLS
				(LIN FT)	(LIN FT)	(LIN FT)	(LIN FT)	(SQ FT)
060-0332	RAMP B	15+06.00	21+91.00	688	685			
060-0250	FAP 310	159+65.00	160+83.00	118	148			
060-0328	FAP 310	160+11.00	161+23.00	112	142			
060-0251	FAP 310	165+06.00	166+38.00	132	176	168	18	16
060-0329	FAP 310	165+45.00	166+60.00	115	145			
TOTAL				1165	1296	168	18	16

POLYUREA PAVEMENT MARKING IS TO BE USED IN PLACE OF THERMOPLASTIC PAVEMENT MARKINGS ON ALL PCC SURFACES

PAVEMENT MARKING REMOVAL				
DESIGNATION	Length (ft)	Size (in)	SQ FT	
US 67 (Godfrey Road)	165+45 to 56+44	2875	4	958.3
IL 111	1172+60 to 1179+40	680	4	226.7
Crossover Det. 1	103+95 to 106+45	123	4	41.0
Connector Det. 1	139+00 to 142+18	369	4	123.0
Connector Det. 2	181+30 to 184+76	413	4	137.7
Crossover Det. 4	226+35 to 229+00	311	4	103.7
Total				1590

PAINT PAVEMENT MARKING CURB	
LOCATION	FOOT
Intersection of US 67 (Godfrey Road) & IL 111	
Island (US 67 to IL 111)	300.0
Median Nose on IL 111	50.0
Island (IL 111 to US 67)	125.0
Intersection of FAP 310 & Lagemann Road	
STA. 167+00	525.0
Burled Left Turn Lane to FE	505.0
Burled Left Turn Lane to Lagemann Road	420.0
STA. 174+50	630.0
Total	2555

TEMPORARY PAVEMENT MARKING						
DESIGNATION	LOCATION		4" YELLOW (LIN FT)	4" WHITE (LIN FT)	24" WHITE (LIN FT)	LTRS & SYM (SQ FT)
	BEGIN STA	END STA				
US 67 (Godfrey Road)	165+45.00	57+00.00	10740	6848	86	218.4
U.S. 67 (Godfrey Road) - FAP 310	57+00.00	103+95	1965			
IL 111	1171+50	1179+40	3000	2620	40	88.4
CONNECTOR DETAIL NO. 1	136+00	142+50	1700	1300		
CROSS OVER DETAIL NO. 1	0+00	7+11	1641	711		
FAP Route 310 SB	111+00	136+00	630	5000		
CROSS OVER DETAIL NO. 2	0+00	13+06	3012	2612		
CONNECTOR DETAIL NO. 2	0+00	5+78	1556	1156		
FAP Route 310 NB	144+25	179+00	870	7870		
CROSS OVER DETAIL NO. 3	0+00	11+85	2770	2370		
CROSS OVER DETAIL NO. 4	0+00	8+04	2008	1608		
FAP Route 310 SB	185+86	217+50	791	6328		
CROSS OVER DETAIL NO. 4 (ST 2)	217+50	227+50	2000	2000		
CROSS OVER DETAIL NO. 4 (ST 3)	217+40	229+00	2310	1550		
TOTAL			34993	41973	126	306.8

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

# SCHEDULES OF QUANTITIES

SCALE: NO SCALE  
DATE: 09-04-09

DRAWN BY: C.J.C.  
CHECKED BY: J.J.C.