

ENTRANCE PIPE CULVERT SCHEDULE

STATION	STAGE CONSTRUCTION	PIPE CULVERTS							
		CLASS D							
		TYPE 1				TYPE 2			
		12"	15"	18"	24"	30"	36"	12"	24"
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
<i>FAP 310</i>									
114+50.00	STAGE 1				54				
121+50.00	STAGE 1	48							
125+86.00	STAGE 1		48						
130+80.00	STAGE 1			48					
148+46.82	STAGE 1					46			
212+26.00	STAGE 1	36							
227+89.00	STAGE 1				54				
<i>Access Rd 1</i>									
12+62.00	STAGE 1	60							
15+00.00	STAGE 1	60							
17+51.00	STAGE 1	60							
18+27.00	STAGE 1	60							
29+00.00	STAGE 1	54							
59+50.00	STAGE 1	48							
72+28.00	STAGE 1	42							
<i>Access Rd 2</i>									
11+50.00	STAGE 1			66					
14+00.00	STAGE 1			60					
14+00.00	STAGE 1			60					
19+00.00	STAGE 1								78
19+00.00	STAGE 1								78
21+92.00	STAGE 1			102					
21+92.00	STAGE 1			102					
24+00.00	STAGE 1			48					
24+00.00	STAGE 1			48					
25+02.50	STAGE 1			48					
25+02.50	STAGE 1			48					
39+00.00	STAGE 1		52						
<i>Access Rd 3</i>									
13+00.00	STAGE 1	54							
14+00.00	STAGE 1	54							
17+50.00	STAGE 1	54							
19+00.00	STAGE 1	60							
20+50.00	STAGE 1	54							
<i>Davis Lane</i>									
07+00.00	STAGE 1								72
08+50.00	STAGE 1								50
<i>Ingham Rd</i>									
08+37.00	STAGE 1	34							
11+16.00	STAGE 1	42							
<i>Lagemann Rd Service Drive</i>									
00+25.00	STAGE 1	42							
01+07.00	STAGE 1	40							
03+09.00	STAGE 1	40							
<i>Lagemann Rd</i>									
16+50.00	STAGE 1	36							
16+50.00	STAGE 1	36							
21+36.77	STAGE 1	78							
22+50.00	STAGE 1	36							
23+90.76	STAGE 1	42							
SUBTOTALS	STAGE 1	1170	100	0	684	54	46	122	156
<i>FAP 310</i>									
128+50.00	STAGE 2			48					
136+80.00	STAGE 2			57					
136+80.00	STAGE 2			57					
SUBTOTALS	STAGE 2	0	0	0	162	0	0	0	0

ENTRANCE PIPE CULVERT SCHEDULE

STATION	STAGE CONSTRUCTION	PIPE CULVERTS							
		CLASS D							
		TYPE 1				TYPE 2			
		12"	15"	18"	24"	30"	36"	12"	24"
FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT		
<i>FAP 310</i>									
142+00.00	STAGE 3				40				
142+00.00	STAGE 3				40				
143+08.00	STAGE 3					48			
143+08.00	STAGE 3					48			
144+28.00	STAGE 3					48			
144+28.00	STAGE 3					48			
170+40.00	STAGE 3				48				
170+40.00	STAGE 3				48				
179+50.00	STAGE 3	50							
184+50.00	STAGE 3	42							
207+00.00	STAGE 3							60	
221+80.00	STAGE 3			66					
221+80.00	STAGE 3			66					
<i>Beuttel Rd</i>									
06+35.00	STAGE 3	44							
07+15.00	STAGE 3	48							
07+15.00	STAGE 3	52							
SUBTOTALS	STAGE 3	236	0	132	176	192	0	60	0
TOTALS		1406	100	132	1022	246	46	182	156

TEMPORARY STRUCTURE

LOCATION	STAGE	STORM SEWER		FLUSH INLET BOX FOR MEDIAN, STANDARD 542546, SPECIAL EACH	MH TY A, SPL 5'-DIA TY 1 F CL EACH
		12"	24"		
		FOOT	FOOT		
<i>Fap 310</i>					
166+00.00 to 167+80.00	STAGE 1	178			
SUBTOTALS		178	0	0	0
<i>Fap 310</i>					
107+50.00	STAGE 2				
135+50.00	STAGE 2			1	
136+50.00	STAGE 2			1	
136+50.00 to 138+00.00	STAGE 2	146			
138+00.00	STAGE 2			1	
138+00.00 to 140+00.00	STAGE 2	196			
140+00.00	STAGE 2			1	
140+00.00 to 141+75.00	STAGE 2		172		
141+75.00	STAGE 2			1	
141+75.00 to 142+50.00	STAGE 2		70		
142+50.00	STAGE 2			1	
142+50.00 to 143+00.00	STAGE 2		46		
143+00.00	STAGE 2				1
SUBTOTALS		342	288	6	1
TOTALS		520	288	6	1

TEMPORARY PIPE CULVERTS

LOCATION	STAGE	PIPE CULVERT CLASS D, TYPE 1				PIPE CULVERT CLASS D, TYPE 2	
		12"	15"	18"	24"	12"	24"
		FOOT	FOOT	FOOT	FOOT	FOOT	FOOT
<i>FAP 310</i>							
111+94.00	STAGE 1		40				
119+00.00	STAGE 1	46					
121+50.00	STAGE 1	46					
125+86.00	STAGE 1		42				
130+80.00	STAGE 1	44					
140+00.00	STAGE 1				74		
171+50.00	STAGE 1		70				
221+97.50 to 222+50.00	STAGE 1				48		
227+89.00	STAGE 1	32					
SUBTOTALS		168	152	0	122	0	0
<i>FAP 310</i>							
107+50.00	STAGE 2		200				
128+50.00	STAGE 2	44					
135+50.00	STAGE 2				14		
143+00.00	STAGE 2						7
144+28.00	STAGE 2	50					
SUBTOTALS		94	200	0	14	0	7
<i>FAP 310</i>							
142+00.00	STAGE 3		34				
143+08.00	STAGE 3		50				
179+50.00	STAGE 3	46					
184+50.00	STAGE 3	38					
189+21.50	STAGE 3					42	
191+75.00	STAGE 3	38					
193+79.00	STAGE 3			38			
197+82.00	STAGE 3		44				
199+33.00	STAGE 3		32				
200+80.00	STAGE 3	30					
207+00.00	STAGE 3	38					
SUBTOTALS		190	160	38	0	42	0
TOTALS		452	512	38	136	42	7

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

## SCHEDULES OF QUANTITIES

SCALE: NO SCALE  
DATE: 02-06-09

DRAWN BY: C.J.C.  
CHECKED BY: J.J.C.