

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE											
				ROADWAY 1000-2A				TRAFFIC SIGNALS Y031-IF			UTILITIES Y060		BOX CULVERT X028-2A	RETAINING WALLS Y007	
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	E. CHURCH ST. 80% FED 10% STATE 10% CITY	MID BLOCK CROSSING 80% FED 20% CITY	MORRISON AVE. 80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	
44200202	PAVEMENT PATCHING, TYPE II, 17 INCH	SQ YD	649			649									
44200204	PAVEMENT PATCHING, TYPE III, 17 INCH	SQ YD	144			144									
44200206	PAVEMENT PATCHING, TYPE IV, 17 INCH	SQ YD	92			92									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	14534	2382		12152									
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1												
50105210	REMOVE EXISTING CULVERTS	FOOT	130			130							1		
50200100	STRUCTURE EXCAVATION	CU YD	330												
50300100	FLOOR DRAINS	EACH	15										69	261	
50300225	CONCRETE STRUCTURES	CU YD	194.7										7	8	
50300300	PROTECTIVE COAT	SQ YD	43										75.7	119	
50500505	STUD SHEAR CONNECTORS	EACH	1018										43		
50700209	UNTREATED TIMBER LAGGING	SQ FT	1738										186	832	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	98347			197							323	1415	
50800515	BAR SPLICERS	EACH	106										83420	14730	
50900200	STEEL RAILING, TYPE 2399	FOOT	171										106		
50901750	PARAPET RAILING	FOOT	350										171		
50901760	PIPE HANDRAIL	FOOT	185			185								350	
*51202220	FURNISHING SOLDIER PILES (BUILT-UP SECTION)	FOOT	122												122
*51202230	FURNISHING SOLDIER PILES (W SECTION)	FOOT	2433												2433
51500100	NAME PLATES	EACH	1										536	1897	
54001001	BOX CULVERT END SECTION, CULVERT NO. 1	EACH	1	1									1		
54001002	BOX CULVERT END SECTION, CULVERT NO. 2	EACH	1	1											
54001003	BOX CULVERT END SECTION, CULVERT NO. 3	EACH	1												
54003000	CONCRETE BOX CULVERTS	CU YD	270.6			1									
54010202	PRECAST CONCRETE BOX CULVERT 2' X 2'	FOOT	71			71							270.6		
54010302	PRECAST CONCRETE BOX CULVERT 3' X 2'	FOOT	365			365									
54010402	PRECAST CONCRETE BOX CULVERT 4' X 2'	FOOT	676			676									
54010403	PRECAST CONCRETE BOX CULVERT 4' X 3'	FOOT	412	412											
54010505	PRECAST CONCRETE BOX CULVERT 5' X 5'	FOOT	142	142											
54010906	PRECAST CONCRETE BOX CULVERT 9' X 6'	FOOT	273	273											
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8	6		2									

FILE NAME =	USER NAME = keplarc1	DESIGNED -	REVISED -
at\pwwork\PIWIDOT\KEPLARCL\dms79807\0816838-shr-plan.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 11/19/2009		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____
--------------	---------------------------------	--------------------------

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	6
CONTRACT NO. 76830			ILLINOIS FED. AID PROJECT	

*Specialty Items

Rev.

Rev. 2-25-10