

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE												
				ROADWAY 1000-2A				TRAFFIC SIGNALS Y031-IF			UTILITIES Y000		BOX CULVERT X02B-24	RETAINING WALLS Y007		
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY E. CHURCH ST. 80% FED 10% STATE 10% CITY	MADISON COUNTY MID BLOCK CROSSING 80% FED 20% CITY	ST. CLAIR COUNTY MORRISON AVE. 80% FED 20% STATE	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY		
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE		
550A0710	STORM SEWERS, CLASS A, TYPE 3 24"	FOOT	240			240										
550A0780	STORM SEWERS, CLASS A, TYPE 3 48"	FOOT	139			139										
550A4800	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 18"	FOOT	141			141										
550A4900	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 24"	FOOT	336			336										
550A5100	STORM SEWERS, CLASS A, TYPE 2 EQUIVALENT ROUND-SIZE 30"	FOOT	129			129										
55100200	STORM SEWER REMOVAL 6"	FOOT	88			88										
55100300	STORM SEWER REMOVAL 8"	FOOT	59			59										
55100400	STORM SEWER REMOVAL 10"	FOOT	90			90										
55100500	STORM SEWER REMOVAL 12"	FOOT	795	384		411										
55100700	STORM SEWER REMOVAL 15"	FOOT	182			182										
55100900	STORM SEWER REMOVAL 18"	FOOT	125			125										
55101200	STORM SEWER REMOVAL 24"	FOOT	639			639										
55101400	STORM SEWER REMOVAL 30"	FOOT	83			83										
55101600	STORM SEWER REMOVAL 36"	FOOT	182			182										
55101800	STORM SEWER REMOVAL 42"	FOOT	43			43										
55101900	STORM SEWER REMOVAL 48"	FOOT	89			89										
55102100	STORM SEWER REMOVAL 60"	FOOT	101	101												
56100500	WATER MAIN 4"	FOOT	92							81	11					
56100600	WATER MAIN 6"	FOOT	1219							46	1173					
56100700	WATER MAIN 8"	FOOT	5299							375	4924					
56200300	WATER SERVICE LINE 1"	FOOT	2618								2618					
56200700	WATER SERVICE LINE 2"	FOOT	955								955					
56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	10								10					
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	7							1	6					
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	119										22	97		
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	435										75	360		

Rev. Rev. 2-18-10

FILE NAME =	USER NAME = keplarcl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwwork\NPWIDOT\KEPLARCL\dms79887\08	6838-shr-plan.dgn	DRAWN -	REVISED -			600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	8	
	PLOT SCALE = 58.3841' / IN.	CHECKED -	REVISED -			CONTRACT NO. 76830					
	PLOT DATE = 11/19/2009	DATE -	REVISED -			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					