

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE										
				ROADWAY				TRAFFIC SIGNALS			UTILITIES		BOX CULVERT	RETAINING WALLS
				I000-2A				Y031-1F			Y060		X028-2A	Y007
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY
CODE NO	ITEM	UNIT		80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	E. CHURCH ST. 80% FED 10% STATE 10% CITY	MID BLOCK CROSSING 80% FED 20% CITY	MORRISON AVE. 80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	37	5		32								
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	1			1								
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	10			10								
60221200	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	2			2								
60223700	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2			2								
60223800	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	16	2		14								
60228110	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2								2			
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	11			11								
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	56	11		45								
60235800	INLETS, TYPE A, TYPE 4 FRAME AND GRATE	EACH	2			2								
60240210	INLETS, TYPE B, TYPE 1 FRAME, OPEN LID	EACH	1			1								
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	18	1		17								
60240303	INLETS, TYPE B, TYPE 9 FRAME AND GRATE	EACH	8			8								
60260050	SANITARY MANHOLES TO BE RECONSTRUCTED	EACH	3								3			
60500040	REMOVING MANHOLES	EACH	4			4								
60500060	REMOVING INLETS	EACH	22	4		18								
60600605	CONCRETE CURB, TYPE B	FOOT	1418			1418								
60602400	CONCRETE GUTTER (SPECIAL)	FOOT	61			61								
60602500	CONCRETE GUTTER, TYPE A	FOOT	232	220		12								
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	775	202		573								
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	12,887	917		11,970								
60608521	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.24	FOOT	665	665										
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	40			40								
*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	262.5	262.5										
*63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	412.5	62.5		350								
*63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	25	25										

\* Specialty Items

Rev.

Rev. 2-19-10

Rev.

FILE NAME =	USER NAME = keplar-cl	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwwork\PIWIDOT\KEPLARCL\dms79887\0878930-shr-plendgn	DRAWN -	REVISED -	600			60-(30,31,128)-1	MADISON/ST. CLAIR	399	9	
PLOT SCALE = 50.3041' / IN.	CHECKED -	REVISED -	CONTRACT NO. 76830							
PLOT DATE = 11/19/2009	DATE -	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							