

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE											
				ROADWAY I000-2A				TRAFFIC SIGNALS			UTILITIES		BOX CULVERT	RETAINING WALLS	
				ST. CLAIR COUNTY		MADISON COUNTY		Y031-1F			Y060		X028-2A	Y007	
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY	MADISON COUNTY E. CHURCH ST. 80% FED 10% STATE 10% CITY	MADISON COUNTY MID BLOCK CROSSING 80% FED 20% CITY	ST. CLAIR COUNTY MORRISON AVE. 80% FED 20% STATE	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY	
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	80					80							
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	5					3	2						
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	1					1							
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	281					225	43	13					
85700100	FULL-ACTUATED CONTROLLER AND TYPE III CABINET	EACH	1						1						
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1					1							
85900100	TRANSCEIVER	EACH	1					1							
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1515					1320	195						
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1530					1320	210						
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2575					2035	540						
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1725					1725							
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	1375					1375							
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	110					100	10						
87502680	TRAFFIC SIGNAL POST, ALUMINUM 14 FT.	EACH	1					1							
87700200	STEEL MAST ARM ASSEMBLY AND POLE, 32 FT.	EACH	2						2						
87700250	STEEL MAST ARM ASSEMBLY AND POLE, 42 FT.	EACH	1					1							
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	2					2							
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1					1							
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3					3							
87800200	CONCRETE FOUNDATION, TYPE D	FOOT	3					3							
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	76					54	22						
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	2						2						
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	10					6	4						

*Specialty Items

FILE NAME =	USER NAME = keplarcl	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
cr\pwwork\VPWIDOT\KEPLARCL\dms79887\08	6830-sht-plan.dgn	DRAWN -	REVISED -			600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	12	
	PLOT SCALE = 50.3041' / IN.	CHECKED -	REVISED -			CONTRACT NO. 16830					
	PLOT DATE = 11/19/2009	DATE -	REVISED -			FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT					

Rev.