

SUMMARY OF QUANTITIES			LABAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE										
				ROADWAY 1000-2A				TRAFFIC SIGNALS Y031-IF			UTILITIES Y060		BOX CULVERT X028-2A	RETAINING WALLS Y007
				ST. CLAIR COUNTY		MADISON COUNTY		MADISON COUNTY E. CHURCH ST. 80% FED 10% STATE 10% CITY	MADISON COUNTY MID BLOCK CROSSING 80% FED 20% CITY	ST. CLAIR COUNTY MORRISON AVE. 80% FED 20% STATE	ST. CLAIR COUNTY	MADISON COUNTY	ST. CLAIR COUNTY	MADISON COUNTY
				80% FED 20% STATE	80% FED 10% STATE 10% CITY	80% FED 20% STATE	80% FED 10% STATE 10% CITY				80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE	80% FED 20% STATE
CODE NO	ITEM	UNIT												
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4					4						
88040260	SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 1-3-SECTION, 1-5-SECTION, BRACKET MOUNTED	EACH	4					4						
88102820	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 2-SECTION BRACKET MOUNTED	EACH	4					2	2					
88200300	TRAFFIC SIGNAL BACKPLATE, PLASTIC	EACH	14					10	4					
88500100	INDUCTIVE LOOP DETECTOR	EACH	10					10						
88600100	DETECTOR LOOP, TYPE I	FOOT	1800					1800						
88600600	DETECTOR LOOP REPLACEMENT	FOOT	475							475				
88800100	PEDESTRIAN PUSH-BUTTON	EACH	10					8	2					
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1					1						
89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	100					100						
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1					1						
89502380	REMOVE EXISTING HANDHOLE	EACH	3					3						
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9					9						
A2001720	TREE, ACER SACCHARUM (SUGAR MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	13			13								
A2006920	TREE, QUERCUS PALUSTRIS (PIN OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	6			6								
A2007120	TREE, QUERCUS RUBRA (RED OAK), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	3			3								
B2001116	TREE, CERCIS CANADENSIS (EASTERN REDBUD) 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	33	9		24								
B2005016	TREE, MALUS SNOWDRIFT (SNOWDRIFT CRAB APPLE), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	21			21								
X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	2							2				
X0321556	SANITARY MANHOLES TO BE ADJUSTED	EACH	11							11				
X0322923	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	163			163								
X0326859	PAVEMENT IMPRINTING	SQ YD	656			656								
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	262										262	
X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	18746										3950	14796
X0324896	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, 2-SECTION, BRACKET MOUNTED	EACH	3					3						

*Specialty Items

Rev.

FILE NAME =	USER NAME = keplarc1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct:\pwwork\PWIDOT\KEPLARCL\dms79807\08	8838-sh-t-plan.dgn	DRAWN -	REVISED -			600	60-(30,31,128)-1	MADISON/ST. CLAIR	399	13	
	PLOT SCALE = 50.3041' / IN.	CHECKED -	REVISED -			CONTRACT NO. 76830					
	PLOT DATE = 11/19/2009	DATE -	REVISED -			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT					