

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 80% FED./ 20% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE URBAN Y032-1F							F.O. BACKBONE CONDUIT, & HANDHOLES	TMC DB OFFICE
CODE NO	ITEM	UNIT	I-55/70/64 MP02.4 STA. 40+87	I-64 MP03.1 STA.59+00	I-64 MP03.9 STA.79+16	I-64 MP04.5 STA.132+88	I-64 MP05.6 STA.182+28	I-64 MP06.9 STA.224+11				
25000210	SEEDING, CLASS 2A	ACRE	2.6							2.6		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	233							233		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	233							233		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	233							233		
25100105	MULCH, METHOD 1	ACRE	26							26		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	259							259		
28000500	INLET AND PIPE PROTECTION	EACH	51							51		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	15	1.5	2	2	2	2	1.5	3.5	0.5	
67100100	MOBILIZATION	L SUM	1	0.1	0.1	0.2	0.1	0.1	0.1	0.3		
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	4							4		
70100430	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	EACH	8							8		
70100825	TRAFFIC CONTROL AND PROTECTION, STANDARD 701456	L SUM	1							1		
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1							1		
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1							1		
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1							1		
80300100	LOCATING UNDERGROUND CABLE	FOOT	15280							15280		
80500100	SERVICE INSTALLATION, TYPE A	EACH	1			1						
81012500	CONDUIT IN TRENCH, 1 1/2" DIA., PVC	FOOT	225			225						
81012800	CONDUIT IN TRENCH, 3" DIA., PVC	FOOT	10			10						
81019100	CONDUIT PUSHED, 6" DIA., GALVANIZED STEEL	FOOT	530							530		
81306400	RELOCATE EXISTING JUNCTION BOX	EACH	1			1						
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	58							58		
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	4		1	1				2		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	21870			235				21635		
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	7			7						
87000105	ELECTRIC CABLE ASSEMBLY IN CONDUIT, 600V (EPR-TYPE TC) 2/C NO. 10 AND NO. 10 GROUND	FOOT	25			25						
87301715	ELECTRIC CABLE IN CONDUIT, COMMUNICATION NO. 18 6 PAIR	FOOT	25			25						
87800210	CONCRETE FOUNDATION, TYPE D (SPECIAL)	FOOT	4			4						
87900100	DRILL EXISTING FOUNDATION	EACH	5							5		