

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 90% FED./ 10% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE URBAN Y032-1F						F.O. BACKBONE CONDUIT, & HANDHOLES	TMC D8 OFFICE
CODE NO	ITEM	UNIT	I-55/70/64 MP02.4 STA. 40+87	I-64 MP03.1 STA.59+00	I-64 MP03.9 STA.79+16	I-64 MP04.5 STA.132+88	I-64 MP05.6 STA.182+28	I-64 MP06.9 STA.224+11			
87900200	DRILL EXISTING HANDHOLE	EACH	10							10	
89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	1		1						
X0322912	3000 LAYER 2 SWITCH	EACH	3			1	1	1			
X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	22854							22854	
X0323150	JUNCTION BOX, ALUMINUM, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	21							21	
X0325075	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., FIBERGLASS BULLET RESISTANT	FOOT	390							390	
X0325076	WIDE AREA NETWORK	L SUM	1								1
X0325077	FIBER OPTIC UTILITY MARKER	EACH	78							78	
86300305	CONTROLLER CABINET TYPE III, SPECIAL	EACH	1				1				
X0325461	GLC-T SFP MODULE	EACH	1				1				
X0325482	REMOVE EXISTING ITS EQUIPMENT	EACH	1		1						
X0325483	SFP-GE-L SFP MODULE	EACH	18	5		2	2	2	5	1	1
X0325484	SFP-GE-Z SFP MODULE	EACH	2	1							1
X0325487	WIRED COMMUNICATION DATA CONVERTOR	EACH	3			1	1	1			
X8110120	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC, TYPE C	FOOT	1256							1256	
X8102020	CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80	FOOT	1825							1825	
X0326091	LIGHT POLE, STEEL 50 FT. WITH CAMERA LOWERING SYSTEM	EACH	1			1					
X0326092	RELOCATE CLOSED CIRCUIT TELEVISION SURVEILLANCE CAMERA SYSTEM	EACH	1			1					
X0326094	RELOCATE EXISTING ITS CONTROLLER CABINET	EACH	1			1					
X0326104	RELOCATE RADAR DETECTOR SYSTEM	EACH	1			1					
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	21635							21635	
X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT	27611							27611	
87301804	ELECTRIC CABLE IN CONDUIT, SERVICE NO. 6 1/C	FOOT	760			760					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1							1	