

SUPERELEVATION TRANSITION DATA TABLES

CURVE RAMP A_C6-1

	STATION	CROSS SLOPE (%)	PGL ELEVATION	LEFT EOP AT 16'
ATTAINMENT	NO ATTAINMENT START AT FULL SUPER AT THE BEGINNING OF THE CURVE			
REMOVAL	10+17.90	5.00%	394.39	395.19
	10+25.00	4.49%	394.35	395.07
	10+50.00	2.71%	394.20	394.63
	10+59.90	2.00%	394.14	394.46

CURVE RAMP A_C6-2

	STATION	CROSS SLOPE (%)	PGL ELEVATION	LEFT EOP AT 16'
ATTAINMENT	15+21.63	2.00%	397.56	397.88
	15+25.00	2.14%	397.66	398.00
	15+50.00	3.17%	398.43	398.94
	15+75.00	4.20%	399.27	399.94
	16+00.00	5.23%	400.17	401.01
	16+25.00	6.26%	401.14	402.14
	16+50.00	7.30%	402.12	403.29
	16+64.63	7.90%	402.70	403.96
FULL SE	16+75.00	7.90%	403.10	404.36
	17+00.00	7.90%	404.09	405.35
	17+25.00	7.90%	405.07	406.33
	17+50.00	7.90%	406.06	407.32
	17+75.00	7.90%	407.04	408.30
	18+00.00	7.90%	408.03	409.29
	18+25.00	7.90%	409.01	410.27
	18+32.53	7.90%	409.30	410.56
REMOVAL	18+50.00	6.93%	409.93	411.04
	18+75.00	5.54%	410.74	411.63
	19+00.00	4.14%	411.42	412.08
	19+25.00	2.75%	411.98	412.42
	19+38.53	2.00%	412.25	412.57

* ALSO SEE GORE GRADING DETAILS FROM STA 16+00.016

CURVE RAMPB-1

	STATION	CROSS SLOPE (%)	PGL ELEVATION	LEFT EOP AT 16'
ATTAINMENT	10+22.43	-0.16%	412.53	412.50
	10+25.00	-0.30%	412.49	412.44
	10+50.00	1.19%	412.14	412.33
	10+75.00	2.41%	411.95	412.34
	11+00.00	3.63%	411.92	412.50
	11+25.00	4.85%	412.04	412.82
	11+50.00	6.07%	412.31	413.28
	11+75.00	7.29%	412.74	413.91
	11+89.43	8.00%	413.06	414.34
FULL SE	12+00.00	8.00%	413.33	414.61
	12+25.00	8.00%	414.05	415.33
	12+50.00	8.00%	414.77	416.05
	12+75.00	8.00%	415.50	416.78
	13+00.00	8.00%	416.23	417.51
REMOVAL	13+00.93	8.00%	416.26	417.54
	13+25.00	7.01%	416.96	418.08
	13+50.00	5.98%	417.68	418.64
	13+75.00	4.95%	418.41	419.20
	14+00.00	3.92%	419.14	419.77
	14+25.00	2.90%	419.87	420.33
	14+50.00	1.87%	420.59	420.89
	14+67.93	1.13%	421.12	421.30

* ALSO SEE GORE GRADING DETAILS FROM STA 16+00.016

CURVE RAMP E-1

	STATION	CROSS SLOPE (%)	PGL ELEVATION	LEFT EOP AT 16'
ATTAINMENT	9+53.80	4.50%	-	-
	10+00.00	5.94%	-	-
	10+30.80	6.90%	-	-
FULL SE	10+50.00	6.90%	-	-
	10+75.00	6.90%	-	-
	11+00.00	6.90%	414.79	415.89
	11+25.00	6.90%	414.70	415.80
	11+50.00	6.90%	414.60	415.70
	11+75.00	6.90%	414.51	415.61
	12+00.00	6.90%	414.41	415.51
	12+25.00	6.90%	414.26	415.36
	12+51.41	6.90%	414.03	415.13
REMOVAL	13+00.00	5.38%	413.37	414.23
	13+25.00	4.60%	412.93	413.67
	13+50.00	3.82%	412.41	413.02
	13+75.00	3.04%	411.81	412.30
	14+00.00	2.26%	411.15	411.51
	14+08.41	2.00%	410.90	411.22

CURVE RAMP E-2

	RAMP E STATION	WB I-64 STATION	CROSS SLOPE (%)	RAMP E PGL ELEVATION	LEFT EOP AT 16'
ATTAINMENT	15+68.01	-	1.50%	405.48	405.72
	15+75.00	-	1.72%	405.24	405.52
	16+00.00	-	2.87%	404.36	404.82
	16+25.00	91+45.78	3.55%	403.49	404.06
	16+50.00	91+71.02	4.23%	402.63	403.31
	16+75.00	91+96.26	4.90%	401.78	402.56
	16+83.01	92+04.35	5.10%	401.50	402.32
FULL SE	17+00.00	92+21.50	5.10%	400.99	401.81
	17+25.00	92+46.68	5.10%	400.23	401.05
REMOVAL	17+49.35	92+71.01	5.10%	399.49	400.31
	17+50.00	92+71.66	5.07%	399.48	400.29
	17+75.00	92+96.65	4.29%	398.83	399.52
	18+00.00	93+21.64	3.51%	398.20	398.76
	18+25.00	93+46.64	2.73%	397.55	397.99
	18+48.35	93+69.98	2.00%	396.98	397.30

* ALSO SEE GORE GRADING DETAILS FROM STA 16+00.016