



EARTHWORK QUANTITIES

FROM STATION	TO STATION	EARTH EXCAVATION	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (NOTE 1)	EMBANKMENT (NOTE 2)	EARTHWORK BALANCE (NOTE 3)
		CU YD	CU YD	CU YD	CU YD
15TH STREET					
3+00.00	13+92.79	1930	1448	1705	-258
BAUGH AVENUE					
5+00.00	7+50.67	310	233	72	161
110+00.00	117+37.25	275	206	210	-4
ST. CLAIR AVENUE					
28+71.01	39+98.39	3164	2373	1887	486
WB I-64					
87+42.35	105+15.26	12018	9014	116	8898
RAMP A					
7+86.07	19+38.53	26434	19826	2784	17042
RAMP B					
10+22.38	15+41.39	3576	2682	504	2178
RAMP E					
10+91.00	16+00.16	3802	2852	7	2845
TOTAL		51509	38632	7285	31347

- EARTHWORK NOTES:**
- ESTIMATED SHRINKAGE FACTOR = 25%
 - APPROXIMATE EMBANKMENT QUANTITY IS SHOWN FOR INFORMATION ONLY.
 - APPROXIMATE EARTHWORK BALANCE IS SHOWN FOR INFORMATION ONLY.
 - APPROXIMATE EARTHWORK BALANCE IS SHOWN FOR INFORMATION ONLY.

