

SIGNING REMOVAL SCHEDULE

LOCATION	OFFSET	REMOVE SIGN PANEL ASSEMBLY TYPE A (EA)	REMOVE SIGN PANEL ASSEMBLY TYPE B (EA)	REMOVE SIGN PANEL TYPE 1 (SQ FT)	REMOVE SIGN PANEL TYPE 2 (SQ FT)	REMOVE OVERHEAD SIGN STRUCTURE - SPAN (EA)	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER (EA)	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED (EA)	REMOVE CONCRETE FOUNDATION - OVERHEAD (EA)
15TH STREET									
2+97.32	29' LT	1							
3+33.01	29' LT	1							
5+47.36	31' LT		1						
7+63.02	30' LT							1	
9+20.61	29' RT		1						
110+47.75	25' RT		1						
10+74.54	24' RT		1						
BAUGH AVE									
5+58.50	30' RT		2						
7+32.73	28' LT						1		1
502+80.69	37' RT	1							
504+16.37	32' RT	1							
509+34.87	23' RT	1							
510+25.00	32' RT								
515+16.86	64' RT			9					
514+38.86	35' LT		1						
111+03.62	28' LT	1							
111+32.91	26' LT	1							
114+31.12	25' LT	1							
ST CLAIR STREET									
29+11.79	27' RT		1						
29+38.63	38' LT	1							
29+93.11	29' LT		1						
32+57.00	38' LT		1						
33+12.36	27' RT		1						
33+13.68	30' LT	1							
35+91.10	LT/RT					1			4
36+96.94	16' RT		1						
37+23.99	15' RT	1							
37+22.99	49' RT	1							
38+55.65	27' LT	1							
39+30.58	36' LT		1						
39+40.14	45' LT	1							
39+53.95	24' RT	1							
43+03.08	44' LT		1						
43+42.32	36' LT	1							
RAMP A									
9+73.02	108' RT				16				
11+73.52	13' RT				16				
RAMP B									
13+73.79	8' LT	1							
RAMP E									
24+01.28	46' RT				20				
WESTBOUND 64									
92+42.60	15' LT			7					
92+95.00	LT/RT					1			4
EASTBOUND 64									
38+82.40	89' RT				20				
40+73.02	99' RT			7					
41+88.66	63' RT				14				
52+29.64	109' RT			7					
TOTAL		17	14	30	86	2	1	1	9

3/17/2010  
\$TIME\$  
\$FILE\$

FILE NAME =  
\$FILEL

USER NAME = default  
PLOT SCALE = 20,0000 1/4 IN.  
PLOT DATE = 3/17/2010

DESIGNED - AGF  
DRAWN - AGF  
CHECKED - MPW  
DATE - 3/19/10

REVISED -  
REVISED -  
REVISED -  
REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING AND SIGNING SCHEDULES

SCALE: N/A SHEET NO. 1 OF 3 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-1-2HB	ST. CLAIR	345	143
CONTRACT NO. 76C49				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				