

SIGNING SCHEDULE									
LOCATION	OFFSET	TYPE	SIZE (IN X IN)	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	RELOCATE SIGN PANEL TYPE 1 (SQ FT)	RELOCATE SIGN PANEL TYPE 2 (SQ FT)	TELESCOPING STEEL SIGN SUPPORT (LF)	DESCRIPTION
N 15TH STREET									
4+10.00	31' RT	R3-2	30 X 30	6.25				14	
5+75.00	31' RT	R3-1	30 X 30	6.25				14	
6+00.00	35' LT	M3-2	30 X 15	3.20				17	
		M1-1	36 X 36	9.00					
		M6-1L	30 X 18	3.75					
9+20.00	28' RT	M4-5	30 X 15	3.20				21	
		M1-1	36 X 36	9.00					
		M1-1	36 X 36	9.00					
		M6-1L	30 X 18	3.75					
9+40.00	26' RT	R3-1	30 X 30	6.25				14	
10+60.00	45' RT	M4-5	30 X 15	3.20				21	
		M1-1	36 X 36	9.00					
		M1-1	36 X 36	9.00					
		M6-1R	30 X 18	3.75					
		M4-5	30 X 15	3.20					
		M3-2	30 X 15	3.20					
		M1-1	36 X 36	9.00					
		M6-3	30 X 18	3.75					
12+75.00	28' RT	W11-2	36 X 36	9.00				15	
13+09.00	28' RT	W10-1	36 DIA	9.00				15	
ST CLAIR									
30+00.00	28' RT	M3-2	30 X 15	3.20				18	
		M1-1	36 X 36	9.00					
		M6-1R	30 X 18	3.75					
31+15.00	50' RT	R1-2	36 X 36	9.00				15	
32+15.00	50' RT	R1-1	36 X 36	9.00				15	
		R5-1	36 X 36	9.00					
32+50.00	37' RT	R1-1	36 X 36	9.00				15	
		R5-1	36 X 36	9.00					
32+50.00	37' RT	R3-1	30 X 30	6.25				14	
32+75.00	28' LT	M3-2	30 X 15	3.20				18	
		M1-1	36 X 36	9.00					
		M6-1L	30 X 18	3.75					
33+00.00	50' RT	R1-1	36 X 36	9.00				17	
		R5-1	36 X 36	9.00					
		R3-2	30 X 30	6.25					
37+20.00	28' RT	R5-1	36 X 36	9.00				15	
	35' LT	R5-1	36 X 36	9.00				15	
38+70.00	30' RT	R5-1A	36 X 24	6.00					
	30' LT	R5-1A	36 X 24	6.00					
BAUGH AVENUE									
5+80.00	21' RT	M4-5	30 X 15	3.20				19	
		M3-2	30 X 15	3.20					
		M1-1	36 X 36	9.00					
		M6-1R	30 X 18	3.75					
6+50.00	50' RT	W9-2	36 X 36	9.00				15	
110+75.00	16' LT	M4-5	30 X 15	3.20				19	
		M3-2	30 X 15	3.20					
		M1-1	36 X 36	9.00					
		M6-1L	30 X 18	3.75					
		R5-1	36 X 36	9.00					
	20' RT	R5-1A	36 X 24	6.00				15	
	27' LT	R5-1A	36 X 24	6.00				15	
113+00.00	27' RT	M4-5	30 X 15	3.20				22	
		M3-2	30 X 15	3.20					
		M1-1	36 X 36	9.00					
		M5-1L	30 X 18	3.75					
		M4-5	30 X 15	3.20					
		M1-1	36 X 36	9.00					
		M1-1	36 X 36	9.00					
		M6-3	30 X 18	3.75					
510+50.00	26' RT	R2-1	30 X 36	7.50				15	
RAMP A									
14+25.00	28' LT	N/A					20.00		EXIT 4 RIGHT (EXISTING)
15+30.00	10' RT	W3-3				9.00		15	SIGNAL AHEAD (EXISTING)
17+50.00	18' RT	R5-1A	36 X 24	6.00				14	
	34' LT	R5-1A	36 X 24	6.00				14	
	29' LT	M3-1	30 X 15	3.20				18	
		M1-1100	36 X 36	9.00					
		M6-1R	30 X 18	3.75					
RAMP B									
13+00.00	30' LT	W4-1R	36 X 36	9.00					
RAMP E									
14+00.00	27' LT	W4-3R	48 X 48		16.00				
16+00.00	17' RT	D10-4	54 X 18						
TOTAL				416	16	9	20	454	

TEMPORARY STRIPING SCHEDULE			
LOCATION	TEMPORARY PAVEMENT MARKING (FT)		LETTERS & SYMBOLS (SQ FT)
	4" LINE	12" LINE	
	SOLID WHITE	SOLID YELLOW	SOLID WHITE
BAUGH AVENUE			
36+80.49 TO 39+88.39	1005		64
15TH STREET			
3+00.00 TO 4+41.81		264	
TOTAL			
	1269	64	32

DELINEATOR SCHEDULE	
LOCATION	DELINEATOR (EA)
RAMP A	11
RAMP B	6
RAMP E	10
TOTAL	27

DELINEATOR REMOVAL SCHEDULE	
LOCATION	DELINEATOR REMOVAL (EA)
RAMP A	7
RAMP E	4
TOTAL	11

PRISMATIC CURB REFLECTOR SCHEDULE		
LOCATION	PRISMATIC CURB REFLECTOR CRYSTAL (EA)	PRISMATIC CURB REFLECTOR AMBER (EA)
15TH ST		12
RAMP A	9	
RAMP B	9	
TOTAL	18	12

3/17/2010 3:11 PM \$

FILE NAME =	USER NAME = default	DESIGNED - AGF	REVISED -
#FILEL		DRAWN - AGF	REVISED -
	PLOT SCALE = 20.0000 1/4 IN.	CHECKED - MPW	REVISED -
	PLOT DATE = 3/17/2010	DATE - 3/19/10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING AND SIGNING SCHEDULES

SCALE: N/A SHEET NO. 3 OF 3 SHEETS STA. N/A TO STA. N/A

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	82-1-2HB	ST. CLAIR	345	145
CONTRACT NO. 76C49				
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				

#FILEL