

PAVEMENT MARKING
(SAFETY AREA 2)

LOCATION			LENGTH	THERMOPLASTIC PAVEMENT MARKING						RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	
				4"			12"	LETTERS & SYMBOLS			ONE WAY AMBER	TWO WAY AMBER
				SOLID WHITE EDGE LINE	SKIP-DASH YELLOW CENTERLINE	SOLID DOUBLE YELLOW LINE - MEDIAN	SOLID YELLOW CENTER LINE	SOLID YELLOW DIAGONAL	LEFT TURN ARROW			
STATION	TO	STATION	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SQ FT	EACH	EACH	EACH
179+10	TO	183+75	465	930	97	1100	380	95	31.2	6	12	10
183+75	TO	189+50	575	1150	288		1150		93.6	7		30
189+50	TO	195+00	550	1100	275		1100		93.6	7		26
195+00	TO	200+75	575	1150	288		1150		93.6	7		30
200+75	TO	202+30	155	310	25	800	110	50		2	8	2
SUB-TOTALS				4640	973	1900	3890	145	312	29	20	98
TOTALS						11403		145	312	29		118

GUARDRAIL REMOVAL SCHEDULE
(SAFETY AREA 2)

LOCATION		STEEL PLATE BEAM GUARD RAIL, REMOVAL
STATION	OFFSET	FOOT
179+54	RT	230
180+67	LT	152
181+83	RT	35
182+17	RT	35
182+19	LT	102
182+52	LT	230
201+00	RT	118
201+76	LT	154
		1056

FILE NAME =	USER NAME = dintelmarjn	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES (SAFETY AREA 2)	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
ct\pw_work\PWIDOT\DINTELMANJN\0153208	876d43-sht-plan.dgn	DRAWN - ---	REVISED - ---			327	17RS-3	MARION	96	19	
	PLOT SCALE = 50.0000 ' / IN.	CHECKED - ---	REVISED - ---			CONTRACT NO. 76D42					
	PLOT DATE = 3/17/2010	DATE - ---	REVISED - ---			FED. ROAD DIST. NO. _ ILLINOIS FED. AID PROJECT					