

SUMMARY OF QUANTITIES

SFTY-2A CONT. MAINTENANCE

SUMMARY OF QUANTITIES			100% STATE	CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	LOCATION 1 X071 MAIN 100% STATE SN 060-0044/5	LOCATION 2 X271 MAIN 100% STATE SN 060-0046/7	LOCATION 3 X071 MAIN 100% STATE SN 060-0051/2	LOCATION 4 X001 MAIN 100% STATE SN 060-0319/20			
58700300	CONCRETE SEALER	SQ FT	3154	1034	1488	632				
59200101	BRIDGE WASHING NO. 1	EACH	1	1						
59200102	BRIDGE WASHING NO. 2	EACH	1	1						
59200103	BRIDGE WASHING NO. 3	EACH	1		1					
59200104	BRIDGE WASHING NO. 4	EACH	1		1					
59200105	BRIDGE WASHING NO. 5	EACH	1			1				
59200106	BRIDGE WASHING NO. 6	EACH	1			1				
59200107	BRIDGE WASHING NO. 7	EACH	1				1			
59200108	BRIDGE WASHING NO. 8	EACH	1				1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	0.75	0.75	0.75	0.75			
67100100	MOBILIZATION	L SUM	1	0.25	0.25	0.25	0.25			
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	3		2	1				
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	0.25	0.25	0.25	0.25			

GENERAL NOTES:

- THE BRIDGES SHALL BE WASHED ACCORDING TO SECTION 592 OF THE STANDARD SPECIFICATIONS, EXCEPT THE CONTRACTOR DOES NOT NEED TO WASH THE UNDERSIDE OF THE DECK NOR THE BEAMS FARTHER THAN 5' FROM AN EXPANSION JOINT. THE CONTRACTOR SHALL WASH THE DECK SURFACE, DRAINS, TOP AND INSIDE PARAPET FACES. THE CONTRACTOR SHALL ALSO WASH ALL BEAM ENDS, BEARINGS, BACKWALLS, AND BEARING SEATS UNDER EXPANSIONS JOINTS. LOCATIONS 7 & 8 HAVE INTEGRAL ABUTMENTS WITHOUT EXPANSION JOINTS; SO NO WORK IS REQUIRED UNDER THOSE 2 BRIDGES.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE THAT NONE OF HIS ACTIVITIES ARE WITHIN 50' OF THE CENTER OF ANY RAILROAD TRACK. THE CONTRACTOR SHALL WASH AREAS UNDER JOINTS WHILE REMAINING AT LEAST 50' FROM ANY RAILROAD TRACK. RAILROAD PROTECTIVE LIABILITY INSURANCE WILL NOT BE REQUIRED FOR THIS CONTRACT.
- ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT ORANGE IN COLOR AND SKID MOUNTED. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED.
- NO OVERNIGHT LANE CLOSURES WILL BE ALLOWED.
- ANY TRAFFIC CONTROL NOT USED SHALL BE DEDUCTED AND NO ADDITIONAL COMPENSATION WILL BE ALLOWED.
- THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO COMMENCING OF WORK AND ORDERING OF MATERIALS.
- IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO ENSURE NO AREAS OUTSIDE OF THE JOB LIMITS ARE DISTURBED. ANY AREAS DISTURBED DUE TO CONSTRUCTION ACTIVITIES SHALL BE SEEDED AT THE CONTRACTOR'S EXPENSE AND NO OTHER COMPENSATION WILL BE PERMITTED.
- CONCRETE SEALER SHALL BE APPLIED TO BEARING SEATS UNDER JOINTS.
- TRAFFIC CONTROL STANDARD 701411 IS FOR THE ENTRANCE AND EXIT RAMPS AT 270 OVER 111 (EB AND WB), AND FOR THE IL 159 ENTRANCE RAMP ONTO I-270 WB (SN 060-0320)

COMMITMENTS

NONE

LIST OF STANDARDS

000001-05 701400-04 701406-05
701901-01 780001-02 701411-06

FILE NAME =	USER NAME = #USER#	DESIGNED <i>A. Vinson</i>	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SOQ, GENERAL NOTES, STANDARDS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
#FILE#		DRAWN <i>A. Vinson</i>	REVISED -			270	D-8 BRIDGE CLEANING 2010-1	MADISON	8	2	
	PLOT SCALE = #SCALE#	CHECKED <i>J. Uehle</i>	REVISED -			CONTRACT NO.					
	PLOT DATE = #DATE#	DATE <i>6-11-2010</i>	REVISED -			SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.