

SUMMARY OF QUANTITIES

*URBAN
100% STATE*

*URBAN
100% STATE*

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		I000			CODE NO	ITEM	UNIT		I000		
20400800	FURNISHED EXCAVATION	CU YD	76	76		54200253	PIPE CULVERTS, CLASS D, TYPE 1 48"	FOOT	50	50			
25000200	SEEDING, CLASS 2	ACRE	0.36	0.36		60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	8	8			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	33	33		60603450	GUTTER INLET (SPECIAL)	EACH	1	1			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	33	33		60615400	PAVED DITCH, TYPE A-15	FOOT	100	100			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	33	33		*63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	3250	3250			
25100115	MULCH, METHOD 2	ACRE	0.36	0.36		*63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	12	12			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	33	33		*63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	12	12			
28100703	STONE DUMPED RIPRAP, CLASS A2	SQ YD	27	27		63200310	GUARDRAIL REMOVAL	FOOT	3591	3591			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	20	20		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	45.9	45.9		67100100	MOBILIZATION	L SUM	1	1			
40600300	AGGREGATE (PRIME COAT)	TON	204	204		70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1			
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	5765	5765		70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	1171	1171		70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1			
40600990	TEMPORARY RAMP	SQ YD	316	316		70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1			
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	11529	11529		70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1			
40800020	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.9	0.9		70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
40800030	AGGREGATE (PRIME COAT)	TON	5	5		70300100	SHORT-TERM PAVEMENT MARKING	FOOT	14376	14376			
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	302	302		70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	724	724			
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	85230	85230		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	115393	115393			
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	64148	64148		70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1410	1410			
44004250	PAVED SHOULDER REMOVAL	SQ YD	62	62		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	931	931			
44200974	CLASS B PATCHES, TYPE III, 10 INCH	SQ YD	26	26		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	178	178			
44200976	CLASS B PATCHES, TYPE IV, 10 INCH	SQ YD	997	997		*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	724	724			
44201007	CLASS B PATCHES, TYPE II, 13 INCH	SQ YD	197	197		*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	115393	115393			
44201013	CLASS B PATCHES, TYPE IV, 13 INCH	SQ YD	660	660		*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1410	1410			
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	13	13		*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	931	931			
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	31	31		*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	681	681			
44213100	PAVEMENT FABRIC	SQ YD	1472	1472		*78200300	PRISMATIC CURB REFLECTOR	EACH	84	84			
44213200	SAW CUTS	FOOT	3576	3576									
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	48	48									
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	2227	2227									
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	62	62									
48203100	HOT-MIX ASPHALT SHOULDERS	TON	1605	1605									

**Specialty Items*

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE. 582	SECTION (4,5RS)	COUNTY MADISON	TOTAL SHEETS 71	SHEET NO. 3
#FILE#		DRAWN -	REVISED -							
		CHECKED -	REVISED -							
		DATE -	REVISED -							
					SCALE:	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT

CONTRACT NO. 76D47