THERMOPLASTIC PAVEMENT MARKING														
	LINE 4"								LINE 12"			LINE 24"	LETTERS & SYMBOLS	
Location	Edgelines (White)	Turn Lanes (White)	Skip-Dash, 2' (White)	Centerline Skip-Dash (White)	Centerline Skip-Dash (Yellow)	No Pass 1-Way (Yellow)	No Pass 2-Way (Yellow)	Median (Yellow)	Crosswalks (white)	Chevrons (Yellow)	Chevrons (White)	Stop Bars (White)	Turn Arrows (White)	RR Crossing (White)
MM 0.00 - 0.20	2112				240	950	1056							
Br. Omission														
MM 0.27 - 1.00	7709				890	1954								
Br. Omission														
MM 1.07 - 2.06	10455				1580	6336	1372							
Br. Omission														
MM 2.13 - 4.90	29251			3350	2400	4277	5492							
MM 4.90 - 6.36				3860			15418							
New Poag Road		334						4072		37		72	62.4	
Madison/Hawthorne		736						3130			331	312	93.6	244.8
Rand								6555				288		244.8
Seventh		295						1295					31.2	
Seventh										83				
Tydeman									190			44		
Thomas									194			44		
Esther									213			44		
Madison (IL 143)		206	68						362			68	31.2	
Alton/Edwardsville												59	15.6	
SUB-TOTALS	49527	1571	68	7210	5110	13517	23338	15052	959	120	331	931	234	489.6
TOTALS	115393								1410			931	723.6	

RAISED REFLECTIVE PAVEMENT MARKERS						
LOCATION	1-WAY CRYSTAL		2-WAY AMBER		1-WAY AMBER	
	REMOVE	NEW	REMOVE	NEW	REMOVE	NEW
MM 0.00 - 1.50			100	100		
MM 1.50 - 1.75	34	34				
MM 1.75 - 3.85			139	139		
MM 3.85 - 6.36	332	332				
New Poag Road	8	8				19
Madison/Hawthorn	19	19				
Seventh	7	7		6		12
Madison (IL 143)	5	5				
TOTALS	405	405	239	245	0	31

LOCATION	PRISMATIC CURB REFLECTOR	PAINT PAVEMENT MARKING CURB
	EACH	FOOT
NEW POAG RD (S SIDE)	40	1024
NEW POAG RD (N SIDE)	40	1024
ALTON/EDWARDSVILLE RD.	4	96
TOTALS	84	2144