MILLING AND RESURFACING											
LOCATION	SQ FT	HMA SURF REM - BT JT	TEMP RAMPS	HMA SURF REM, 3/4"	HMA SURF REM, 2-1/4"	HMA SURF CSE, MIX D, N90	LEVELING BINDER (MM), N90	HMA SHOULDERS	HMA SHOULDERS 8'	PAVED SHOULDER REMOVAL	AGGREGATE WEDGE SHOULDER, TYPE B
		SQ YD	SQ YD	SQ YD	SQ YD	TON	TON	TON	SQ YD	SQ YD	TON
MM 0.00 - 0.20	27456	96.6	19.4	3050.7		256.3	128.1	21.3			82.1
Bridge Omission											
MM 0.27 - 1.00	100214.4	106.6	21.4	11134.9		935.3	467.7	28.1	33.3	33.3	299.8
Bridge Omission											
MM 1.06 - 1.39	45302.4	53.3	10.7	5033.6		422.8	211.4		27.8	27.8	135.5
MM 1.39 - 1.94	216415.8				24046.2	1626.2	813.1	603.2			112.9
MM 1.94 - 2.02	10982.4			1220.3		102.5	51.3				32.9
MM 2.02 - 2.06	6758.4	53.3	10.7	750.9		47.3	23.7	23.6			21.9
Bridge Omission											
MM 2.13 - 2.17	6758.4	53.3	10.7	750.9		47.3	23.7	23.6			21.9
MM 2.17 - 3.83	227884.8			25320.5		2126.9	1063.5				681.7
MM 3.83 - 4.85	323136	285	57	35904		2412.7	1206.4	904.8			837.7
MM 4.85 - 4.95	28512	261.6	52.4		3168	266.1	133.1				
MM 4.95 - 5.31	83635.2				9292.8	780.6	390.3				
MM 5.31 - 6.10	183532.8				20392.5	1713	856.5				
MM 6.10 - 6.33	55862.4				6206.9	521.4	260.7				
MM 6.33 - 6.36	9371.1	260.8	133.3		1041.2	87.5	43.7				
Madison/Hawthorn	16607.2			1845.2		155	77.5				
Rand Int.	1964.1			218.2		18.3	9.2				
TOTALS		1170.5	315.6	85229.2	64147.6	11528.1	5764.4	1604.6	61.1	61.1	2226.4

INCIDENTAL HMA SURFACING	
LOCATION	TON
CROSSOVERS	
N. of Madison/Hawthor	95.0
S. of Rand	44.6
N. of Velma	50.2
SIDEROADS	
Old Poag Road	4.9
Artmore Dr.	7.0
Lake Front Dr.	10.5
Frontage Road	2.8
Frontage Road	2.1
Canal Road	3.5
Kearby Lane	3.5
Wagon Wheel Road	8.4
Robbins Road	5.3
Braodway Ave.	10.5
Daniel Boone Trail	7.0
Velma	3.5
Madison/Hawthorne	22.7
Rand	14.0
DRIVEWAYS	5.8
TOTAL	301.3